

Alamo Colleges WFAC Black Box Addition PKG 1

1801 Martin Luther King Dr.,
San Antonio, TX, 78203

ISSUE FOR CONSTRUCTION

2024/06/14



BOARD OF TRUSTEES

JOE ALDERETE JR.
GLORIA RAY
ANNA URIEGAS BUSTAMANTE
DR. LORENA PULIDO
ROBERTO ZÁRATE
DR. GENE SPRAGUE
DR. YVONNE KATZ
CLINT KINGSBERY
LESLIE SACHANOWICZ
BRANDON AVIADO

DISTRICT 1
ASSISTANT SECRETARY, DISTRICT 2
DISTRICT 3
SECRETARY, DISTRICT 4
DISTRICT 5
DISTRICT 6
DISTRICT 7
VICE CHAIR, DISTRICT 8
DISTRICT 9
STUDENT TRUSTEE

ADMINISTRATION

DR. ADENA WILLIAMS LOSTON
RANDALL DAWSON
WESLEY B. WELLS
GEORGE H. JOHNSON, III
CHRISTOPHER METSGAR
DR. KIMBERLEY IRVING-CONAWAY
DR. DIANE GAVIN
MARSHA P. HALL

PRESIDENT
VICE-PRESIDENT FOR ACADEMIC SUCCESS
VICE-PRESIDENT FOR STUDENT SUCCESS
INTERIM VICE-PRESIDENT FOR COLLEGE
DEAN FOR ACADEMIC SUCCESS, HEALTH SCIENCES
DEADN FOR ACADEMIC SUCCESS, ACADEMIC SERVICES
DEAN OF PERFORMANCE EXCELLENCE
DIRECTOR OF STRATEGIC INITIATIVES

ARCHITECT
PBK ARCHITECTS, INC
601N.W.LOOP 410, Suite 400
San Antonio, TX 78216
T 210-829-0123

ASSOCIATE ARCHITECT
B&A ARCHITECTS
222 Ridgcrest Dr
San Antonio, TX 78209
T 210-829-1898

CIVIL ENGINEER
GESSNER
401 W. 26th St, Ste 3
Bryan, TX 77803
T 979-680-8840

STRUCTURAL ENGINEER
LUNDY & FRANKE ENGINEERING
549 Heimer
San Antonio, TX 78232
T 210-979-7900

LANDSCAPE ARCHITECT
EDGELAND GROUP
11 Greenway Plaza, 15th Floor
Houston, TX 77046
T 713-460-0988

MEP ENGINEER
LEAF
601N.W.LOOP 410, Suite 400
San Antonio, TX 78216
T 210-829-0123

THEATER CONSULTANT
WJHW
12175 Network Blvd., Suite 150
San Antonio, TX, 78249
T 210-561-9800

ENVELOPE CONSULTANT
BEAM PROFESSIONALS
601N.W.LOOP 410, Suite 400
San Antonio, TX 78216
T 210-829-0123

WFAC Black Box Addition PKG 1

1801 Martin Luther King Dr.,
San Antonio, TX, 78203
ISSUE FOR CONSTRUCTION

SHEET NUMBER	SHEET NAME
G-000	ARCHITECTURAL GENERAL
G-001	COVER SHEET
G-002	GENERAL PROJECT INFORMATION
G-021	TEXAS ACCESSIBILITY STANDARDS
CIVIL	
C100	NOTES
C200	SITE PLAN
C201	SITE FIRE PLAN
C202	DIMENSION CONTROL & PAVING PLAN
C300	EXISTING CONDITIONS & DEMO PLAN
C400	GRADING PLAN
C401	CRAWLSPACE
C500	PRE DRAINAGE AREA MAP
C501	POST DRAINAGE AREA MAP
O600	OVERALL UTILITY
O700	ELEC. & COMMS PLAN & PROFILES
C800	STORM PLAN
C801	STORM PROFILES
C900	SANITARY PLAN & PROFILES
C1000	WATER PLAN & PROFILES
C1100	EROSION CONTROL
C1200	DETAILS
C1201	DETAILS
C1202	DETAILS
STRUCTURAL	
S-101	NOTES, SECTIONS & DETAILS
S-102	SPECIAL INFECTION NOTES
S-201	FOUNDATION FRAMING PLAN
S-301	SECTIONS & DETAILS & MECH. YARD FOUNDATION
S-302	SECTION
S-303	SECTION
S-304	SECTION
S-305	SECTION
S-306	SECTION
S-307	SECTIONS
S-308	SECTIONS
S-309	SECTIONS
S-401	CONC. BEAM SCHED. & NOTES
S-402	CONC. JOIST SCHED. NOTES & DETAILS
ARCHITECTURAL SITE DEMOLITION	
ASD101	DEMOLITION ARCHITECTURAL SITE PLAN
ARCHITECTURAL SITE	
AS100	ARCHITECTURAL SITE PLAN
AS401	ARCHITECTURAL ENLARGED SITE PLANS
ARCHITECTURAL	
A-100	CRAWLSPACE FLOOR PLAN - COMPOSITE
A-411	DOOR SCHEDULE PANEL AND FRAME TYPES
MECHANICAL	
MPS-101	MECHANICAL AND PLUMBING SITE PLAN
ELECTRICAL	
E05-101	DEMO SITE POWER PLAN
E101	ELECTRICAL ONE LINE DIAGRAM
E-502	ELECTRICAL RISER DIAGRAM
E-601	ELECTRICAL SYMBOL LEGEND AND CONTRACTOR SCHEDULE
E-602	ELECTRICAL DETAILS
E-603	ELECTRICAL DETAILS
ES-101	SITE POWER PLAN
PLUMBING	
P-000	SYMBOLS AND ABBREVIATIONS
PL-101-A	CRAWLSPACE PLUMBING PLAN
P-601	PLUMBING DETAILS
P-602	PLUMBING DETAILS
TECHNOLOGY	
T-001	TECHNOLOGY SYSTEM NOTES AND LEGENDS
TS-101	SITE TECHNOLOGY PLAN

ADD ALTERNATES

- PROVIDE SEPARATE PRICING TO REMOVE THE LOBBY ADDITION IN FRONT OF THE EXISTING WATSON THEATER ENTRANCE. THIS IS TO INCLUDE PIERS, FOUNDATION.
- MUD SLAB:
2A - PROVIDE SEPARATE PRICING TO REMOVE MUD SLAB DOWN TO A PATHWAYS FROM THE FLOOR HATCH TO THE PLUMBING DRAINS. REFER TO SHEET A-100.
2B - PROVIDE SEPARATE PRICING TO REMOVE THE MUD SLAB.

ABBREVIATIONS AND LEGEND KEYS

REFER TO SCHEDULES AND LEGENDS FOR ADDITIONAL ABBREVIATIONS REFER TO OTHER DISCIPLINES FOR ADDITIONAL ABBREVIATIONS

A	above	FG	finish group	PERM	perimeter	T	tread
ABV	above	FHC	fire hydrant	PG	paint grade	TAG	torque & groove
ACOUS	acoustical	FH	fire hose cabinet	PLAM	plastic laminate	T.O.	top of
ACT	acoustical ceiling tile	FLR	floor	PLAS	plaster	TEL	telephone
AD	adjustable	FLR	floor	PLYWD	plywood	TER	terrazzo
ADJ	adjustable	FLUOR	fluorescent	POLYISO	polyisocyanurate	THK	thick
AFF	above finished floor	FT	foot or feet	PR	pair	THR	threshold
ALT	alternate	FUR	furring	PTD	painted	TYP	typical
ALUM	aluminum	G	gallon	R	riser	U	undercut
APPROX	approximate	GAL	gallon	RAD	radius	UNFN	unfinished
ARCH	architect / architectural	GBV	galvanized	RCP	reflected ceiling plan	UNO	unless noted otherwise
B	bottom of	GB	grab bar	RD	roof drain	UON	unless otherwise noted
BALC	balcony	GC	general contractor	RE	refer	UTIL	utility
BD	board	GL	glass	REF	refrigerator	V	vertical
BET	between	GND	ground	REINF	reinforced	VCT	vinyl composition tile
BLDG	building	GYP	gypsum wall board	REQD	required	VERT	vertical
BLKG	blocking	H	hole	RESL	resilient	VF	verify in field
BLW	below	H.W.H.	hot water heater	RM	room	VTR	vent termination pipe
BM	beam	HW	handicapped	RO	rough opening	VWC	vinyl wall covering
BOT	bottom	HCW	hardwood	RTU	roof top unit (mech)	W	west
BRKT	bracket	HD	hardwood	S	south	W	with
BULKHD	bulkhead	HM	hollow metal	SCHD	schedule	WO	without
BUR	built up roof	HORZ	horizontal	SECT	section	WC	water closet
C	corner guard	HR	hour	SECT	section	WIN	window
C.G.	corner guard	HT	height	SF	square foot	WP	waterproof
CAB	cabinet	HT	hour	SHT	sheet	WS	wetstack
CAK	caulking	HT	height	SIM	similar	WSCT	wainscot
CEM	cement	I	inner diameter	SPEC	specification	X	weight
CER	ceramic	INCAN	incandescent	SS	stainless steel	XPS	extruded polystyrene
CJ	control joint	INSUL	insulation	STD	standard		
CLG	ceiling	INT	interior	STL	steel		
CLS	cleat	JAN	janitor	STOR	storage		
CLR	clear	JST	joist	STRUC	structural		
CO	cased opening	JT	joint	SUSP	suspended		
COL	column	CONT	continuous	SYM	symmetrical		
CONC	concrete	CPT	carpet				
CONT	continuous	CT	ceramic tile				
CPT	carpet	CTR	center				
CT	ceramic tile						
CTR	center						
D	double						
DBL	double						
DET	detail						
DIA	diameter						
DM	dimension						
DN	down						
DR	door						
DS	down spout						
DW	dishwasher						
DWG	drawing						
E	east						
EA	each						
EPFS	exterior insulation & finish system						
ELEC	electrical						
ELEV	elevation						
EMER	emergency						
ENCL	enclosure						
EOS	edge of slab						
EQ	equipment						
EQUIP	equipment						
ETR	existing to remain						
EW	each way						
EXP. JT.	expansion joint						
EXST	existing						
F	face of						
F.O.	face of						
FA	fire alarm						
FAP	fire annunciator panel						
FD	floor drain						
FE	fire extinguisher						
FEC	fire extinguisher cabinet						

GENERAL NOTES


- THE CONTRACT DOCUMENTS ARE TO INCLUDE AIA DOCUMENT A201 "GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION". CLIENT SHALL BE DESIGNATED AS "THE OWNER". PBK ARCHITECTS, INC. SHALL BE DESIGNATED AS "THE ARCHITECT". FACILITY SHALL BE DESIGNATED AS "THE LANDLORD". THE CONTRACT DOCUMENT SHALL ALSO INCLUDE THE AGREEMENT, PERFORMANCE AND PAYMENT BONDS, GENERAL CONDITIONS, SUPPLEMENTARY CONDITIONS, THE SPECIFICATIONS, CONTRACT DRAWINGS ADDENDA, AND CONTRACT MODIFICATIONS, BUILDING RULES AND REGULATIONS & ANY OTHER DOCUMENTS REQUIRED BY THE OWNER.
- THE WORK SHALL BE DONE IN ACCORDANCE WITH THE RULES AND REGULATIONS OF ALL APPLICABLE SAFETY AND BUILDING CODES, AND AS APPROVED BY THE AUTHORITY HAVING JURISDICTION. CONTRACTOR IS RESPONSIBLE FOR SECURING AND PAYING FOR ALL PERMITS REQUIRED FOR THE WORK AND FOR THE SCHEDULING OF ALL REQUIRED INSPECTIONS DURING THE COURSE OF THE WORK.
- CONTRACTOR SHALL REVIEW AND VERIFY EXISTING CONDITIONS AS PROVIDED IN THE CONSTRUCTION DOCUMENTS. CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ALL DISCREPANCIES, ERRORS, INCONSISTENCIES OR AMBIGUITIES PRIOR TO PROCEEDING WITH THE WORK.
- CONTRACTOR SHALL BE RESPONSIBLE FOR, AND PROVIDE PROTECTION OF, ANY EXISTING FINISHES, MATERIALS, AND EQUIPMENT TO REMAIN. CONTRACTOR SHALL REPAIR OR REPLACE ANY DAMAGED FINISHES, MATERIALS, AND EQUIPMENT AS A RESULT OF THE WORK. ALL EXISTING FINISHES TO REMAIN SHALL BE CLEANED AT THE COMPLETION OF CONSTRUCTION. CONTRACTOR SHALL PHOTOGRAPH AND DOCUMENT ALL EXISTING DAMAGES, AND PROVIDE TO THE ARCHITECT, PRIOR TO PROCEEDING WITH THE WORK.
- ALL MATERIALS AND SYSTEMS SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. ALL CONSTRUCTION SHALL BE OF INDUSTRY STANDARD OR BETTER. THE ARCHITECT SHALL BE FINAL JUDGE OF QUALITY.
- ONLY NEW MATERIALS AND EQUIPMENT OF RECENT MANUFACTURE, OF STANDARD QUALITY, AND FREE FROM DEFECTS, WILL BE PERMITTED IN THE WORK, UNLESS OTHERWISE NOTED. REJECTED MATERIALS AND EQUIPMENT SHALL BE REMOVED IMMEDIATELY FROM THE WORK AND RE-PRICED WITH MATERIALS AND EQUIPMENT OF THE QUALITY SPECIFIED. FAILURE TO REMOVE REJECTED MATERIALS AND EQUIPMENT SHALL NOT RELIEVE CONTRACTOR FROM THE RESPONSIBILITY FOR QUALITY OF MATERIAL AND EQUIPMENT USED NOR FROM ANY OTHER OBLIGATION IMPOSED BY THE CONTRACT.
- DO NOT SCALE DRAWINGS. STATED & WRITTEN DIMENSIONS GOVERN. CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN THE FIELD AND SHALL BE RESPONSIBLE FOR THEIR ACCURACY. NO EXTRA CHARGE OR COMPENSATION SHALL BE ALLOWED BECAUSE OF DIFFERENCE BETWEEN ACTUAL DIMENSIONS AND THOSE INDICATED ON THE DRAWINGS, UNLESS THEY CONTRIBUTE TO A CHANGE IN THE SCOPE OF THE WORK. ANY DIFFERENCE FOUND SHALL BE SUBMITTED TO THE ARCHITECT FOR COORDINATION PRIOR TO ORDERING, MANUFACTURING, OR PROCEEDING WITH THE WORK. HORIZONTAL DIMENSIONS INDICATED ARE TO/FROM FACE OF FINISH, UNLESS NOTED OTHERWISE. VERTICAL DIMENSIONS ARE FROM TOP OF FLOOR SLAB EXCEPT WHERE NOTED TO BE ABOVE FINISHED FLOOR (AFF). DIMENSIONS ARE NOT ADJUSTED WITHOUT APPROVAL OF ARCHITECT UNLESS NOTED OTHERWISE.
- CONTRACTOR SHALL VERIFY THAT NO CONFLICTS EXIST BETWEEN THE LOCATIONS OF EXISTING AND PROPOSED NEW MECHANICAL, ELECTRICAL, PLUMBING, DATA, AND SPRINKLER EQUIPMENT (INCLUDING BUT NOT LIMITED TO STRUCTURAL MEMBERS, PIPING, DUCT WORK, CONDUIT AND SPRINKLERS) AND THAT CLEARANCES FOR INSTALLATION AND MAINTENANCE OF EQUIPMENT ARE PROVIDED. ELEMENTS IN CONFLICT SHALL BE DOCUMENTED AND PROVIDED TO THE ARCHITECT PRIOR TO PROCEEDING WITH THE WORK.
- CONTRACTOR SHALL PROVIDE THE ARCHITECT WITH SHOP DRAWINGS FOR REVIEW AND APPROVAL FOR ALL, BUT NOT LIMITED TO, THE FOLLOWING: SHOP-FABRICATED MILLWORK, CARPET LAYOUT, FLOORING, LIGHT FIXTURES, DOORS, MISC. STEEL, METAL FABRICATION, GLASS/GLAZING, SPRINKLER LAYOUTS, HARDWARE. SHOP DRAWINGS SHALL BE SUBMITTED IN THE FORM OF 3 SETS OF PRINTS. SHOP DRAWINGS SHALL NOT BE REPRODUCTIONS OF CONTRACT DOCUMENTS. MATERIAL SUBMITTALS (S SAMPLES) SHALL BE PROVIDED FOR WOOD, FASTENERS, ACRYLIC, CARPET, TILE, BASE, PAINT, LAMINATE AND ANY OTHER MATERIALS INDICATED IN THE SHOP DRAWINGS.
- CONTRACTOR SHALL PROVIDE THE ARCHITECT WITH MANUFACTURER'S CUT SHEETS AND SPECIFICATIONS FOR ALL EQUIPMENT INCLUDING BUT NOT LIMITED TO LIGHT FIXTURES, PLUMBING EQUIPMENT, ELECTRICAL EQUIPMENT, FANS, SUPPLEMENTARY HEATING AND COOLING ELEMENTS, ALL HARDWARE AND SECURITY EQUIPMENT.
- CONTRACTOR SHALL NOT PROCEED WITH WORK FOR WHICH ADDITIONAL COMPENSATION BEYOND THE CONTRACT AMOUNT IS EXPECTED WITHOUT WRITTEN AUTHORIZATION FROM THE ARCHITECT AND OWNER. FAILURE TO OBTAIN SUCH AUTHORIZATION SHALL INVALIDATE A CLAIM FOR EXTRA COMPENSATION. CONTRACTOR SHALL NOT PROCEED WITH WORK WHICH, IF COMPLETED, IS STRICT CONFORMANCE WITH THE CONSTRUCTION DOCUMENTS. WILL RESULT IN ADDITIONAL WORK BEYOND THE SCOPE OF THE CONTRACT WITHOUT WRITTEN AUTHORIZATION FROM THE ARCHITECT AND OWNER. ANY FIELD CONDITIONS THAT SIGNIFICANTLY VARY FROM THE CONTRACT DOCUMENTS OR WILL RESULT IN ADDITIONAL WORK, SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO PROCEEDING WITH WORK.
- PATCH, REPAIR, AND INSTALL ALL FIREPROOFINGS AS REQUIRED BY CODE. FIREPROOF ALL NEW PENETRATIONS AS REQUIRED FOR APPROVAL BY THE AUTHORITY HAVING JURISDICTION.
- WHERE BUILDING THERMAL EXPANSION JOINTS ARE REQUIRED, CONTRACTOR SHALL COMPLY WITH APPLICABLE CODE AND INDUSTRY BEST PRACTICES FOR ROUTING OF ALL PIPING, DUCTS, CONDUITS AND OTHER CONTINUOUS RUNS.
- CONTRACTOR SHALL CONTINUOUSLY CHECK ARCHITECTURAL AND STRUCTURAL CLEARANCES FOR ACCESSIBILITY OF EQUIPMENT AND MECHANICAL AND ELECTRICAL SYSTEMS. NO ALLOWANCES OF ANY KIND WILL BE MADE FOR THE GENERAL CONTRACTOR'S NEGLIGENCE TO FORESEE MEANS OF INSTALLING EQUIPMENT INTO POSITION.
- FINISHED WORK SHALL BE FIRM, WELL-ANCHORED, IN TRUE ALIGNMENT, PLUMB, LEVEL, WITH SMOOTH, CLEAN, UNIFORM APPEARANCE WITHOUT WAVES, DISTORTIONS, HOLES, MARKS, CRACKS, STAINS, OR DISCOLORATION. JOINTING SHALL BE CLOSE FITTING, NEAT AND WELL SCURED. FINISHED WORK SHALL HAVE NO EXPOSED UNSIGHTLY ANCHORS OR FASTENERS AND SHALL NOT PRESENT HAZARDOUS, UNSAFE CORNERS. ALL WORK SHALL HAVE THE PROVISION FOR EXPANSION, CONTRACTION AND SHRINKAGE AS NECESSARY TO PREVENT CRACKS, BUCKLING, AND WARPING DUE TO TEMPERATURE AND HUMIDITY CONDITIONS.
- ATTACHMENTS, CONNECTIONS OR FASTENERS OF ANY NATURE ARE TO PROPERLY AND PERMANENTLY BE SECURED IN CONFORMANCE WITH INDUSTRY BEST PRACTICES. THE DRAWINGS HIGHLIGHT SPECIAL CONDITIONS ONLY AND BY NO MEANS ILLUSTRATE EVERY CONNECTION. THE CONTRACTOR IS RESPONSIBLE FOR IMPROVING CONNECTION ACCORDINGLY.
- CONTRACTOR SHALL WAIVE "COMMON PRACTICE" AND "COMMON CRITERIA" AS CONSTRUCTION CRITERIA WHEREVER DETAILS AND CONTRACT DOCUMENTS OR GOVERNING CODES, ORDINANCES, ETC. REQUIRE QUANTITY OR BETTER QUALITY THAN COMMON PRACTICE OR COMMON USAGE WOULD REQUIRE.
- CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND SUBMITTALS AND SHALL ORDER AND SCHEDULE DELIVERY OF MATERIALS TO AVOID DELAYS IN CONSTRUCTION. IF AN ITEM IS FOUND TO BE UNAVAILABLE OR TO HAVE A LONG LEAD TIME, THE GENERAL CONTRACTOR SHALL NOTIFY ARCHITECT IMMEDIATELY WITH A PROPOSED ALTERNATIVE.
- CONTRACTOR SHALL NOTIFY THE OWNER, THE LANDLORD, AND THE ARCHITECT IN WRITING OF ANY DEFICIENCIES IN BASE BUILDING WORK PRIOR TO THE COMMENCEMENT OF THE WORK. ANY UNREPORTED DEFICIENCIES WILL BECOME THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO CORRECT.
- CONTRACTOR SHALL EXERCISE INDUSTRY BEST PRACTICES FOR CARE AND CAUTION DURING THE CONSTRUCTION OF THE WORK, AND SHALL SCHEDULE WORK TO MINIMIZE DISTURBANCES TO OCCUPANTS. ADJACENT SPACES AND/OR STRUCTURES, PROPERTY, PUBLIC THOROUGHFARES, ETC. THE GENERAL CONTRACTOR SHALL TAKE PRECAUTIONS AND BE RESPONSIBLE FOR THE SAFETY OF ALL BUILDING OCCUPANTS DURING CONSTRUCTION PROCEDURES. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR ANY COSTS INCURRED.
- ALL DEBRIS SHALL BE REMOVED FROM THE SITE ON A DAILY BASIS, OR AS DIRECTED BY THE AUTHORITY HAVING JURISDICTION. UPON COMPLETION OF THE WORK, REMOVE ALL DEBRIS FROM THE WORK PROVIDED UNDER THIS CONTRACT AND LEAVE ALL AREAS CLEAN. TRASH IS NOT PERMITTED TO BE BURNED ON SITE.
- ALL ABANDONED AND MISCELLANEOUS NAILS, HANGERS, STAPLES, WIRES, CONDUITS AND DEBRIS SHALL BE REMOVED FROM EXPOSED AREAS OF THE FLOORS, WALLS, AND CEILINGS. REMOVE ALL ABANDONED PIPE SLEEVES IN FLOOR SLABS. PATCH EXISTING SLAB AS REQUIRED TO MAINTAIN UL FIRE RATING OF FLOOR SLAB WHERE PIPES AND CONDUITS HAVE BEEN REMOVED.
- SLAB PENETRATIONS SHALL BE SEALED AS REQUIRED TO MAINTAIN FIRE RATING, USING MATERIALS AND METHODS APPROVED BY THE AUTHORITY HAVING JURISDICTION. EXPANSION MATERIAL SHALL BE APPROVED BY THE ARCHITECT.
- CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY ACCESS PANELS WHICH MAY BE REQUIRED PRIOR TO PROCEEDING WITH THE WORK. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL TRADES. REQUIRED ACCESS PANELS SHALL BE INCLUDED IN THE CONTRACTOR'S SCOPE OF WORK.
- CONTRACTOR SHALL PROVIDE THE TEAM WITH A CONSTRUCTION SCHEDULE SHOWING THE PROPOSED PHASING. LONG LEAD ITEMS THAT WILL AFFECT THE SUBSTANTIAL COMPLETION DATE SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION IMMEDIATELY.


PROJECT GRAPHIC REFERENCES

DISCIPLINE	SUBDISCIPLINE	0	GENERAL
-	NOT USED	1	PLANS (Site, Floor, Finish, Graphics)
G	GENERAL	2	CEILING
C	CIVIL	3	ROOF
CA	SPORTS CIVIL	4	ENLARGED PLANS
SA	SPORTS ARCH	5	ELEVATIONS (exterior & interior)
S	STRUCTURAL	6	SECTIONS (Big & Wall)
L	LANDSCAPE	7	BLDG DETAILS
D	DEMOLITION	8	DIAGRAMS/COMPILED SCHEDULES (Partition Types, Casework/Work, Door & Panel/Frame Types, Window Types)
A	ARCHITECTURAL	9	MISCELLANEOUS
M	MECHANICAL		
E	ELECTRICAL		
P	PLUMBING		
T	TECHNOLOGY		
FS	FOOD SERVICE		
AV	ACOUSTICAL		
TH	THEATRICAL		

PROJECT GRAPHIC REFERENCES


PROJECT SYMBOLS	PROJECT SYMBOLS	CONSTRUCTION TYPE SYMBOLS






ARCHITECT: SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608


WFCAC Black Box Addition PKG 1



KEY PLAN
NORTH, PLAN, TRUE



ALAMO COLLEGES
ST. PHILIP'S COLLEGE



REGISTERED ARCHITECT
STATE OF TEXAS
1985

CLIENT: Alamo Colleges
DATE: 2024/06/14 PROJECT NUMBER: 230462

No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER: 1

GENERAL PROJECT INFORMATION

G-002


ISSUE FOR PERMIT

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA ARCHITECTS
DESIGNER	BA ARCHITECTS
LANDSCAPE ARCHITECT	BA ARCHITECTS
MECHANICAL ENGINEER	LUNDY & HARRIS ENGINEERING
ELECTRICAL ENGINEER	WATSON FINE ART CENTER
PLUMBING ENGINEER	WATSON FINE ART CENTER
PROVIDER	WATSON FINE ART CENTER
MEASUREMENT	WATSON FINE ART CENTER
TEAM	WATSON FINE ART CENTER

WFAC Black Box Addition PKG 1




CLIENT		Alamo Colleges
DATE	2024/06/12	PROJECT NUMBER
		230462
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER

SITE PLAN

C200



LEGEND

- PROPOSED ASPHALT PAVEMENT
- PROPOSED STRUCTURAL PAVEMENT
- PROPOSED 4" CONCRETE SIDEWALK
- PROPOSED BUILDING
- EXISTING PAVEMENT EDGE
- PROPERTY LINE
- EXISTING EASEMENT
- PROPOSED EASEMENT
- EXISTING CONTOURS
- PROPOSED CONTOURS
- EX. I PROP. STORM LINE
- EX. I PROP. WATER LINE
- EX. I PROP. SANITARY SEWER LINE
- EXISTING THERMALS
- PROPOSED THERMALS
- EX. I PROP. GAS LINE
- EX. I PROP. DATA/TELECOM
- EX. I PROP. UNDERGROUND ELECTRIC
- EX. I PROP. FIBER OPTIC
- EX. I PROP. OVERHEAD ELECTRIC
- EX. I PROP. FIRE HYDRANT
- EX. I PROP. WATER METER
- EX. I PROP. GATE VALVE
- EX. IRRIGATION CONTROL VALVE
- PROP. FIRE DEPARTMENT CONNECTION
- PROP. POST INDICATOR VALVE
- PROP. HOSE LAY
- EX. I PROP. SANITARY SEWER MANHOLE
- EX. I PROP. SANITARY SEWER CLEANOUT
- EX. STORM SEWER MANHOLE
- PROP. STORM SEWER CURB INLET
- EX. I PROP. LIGHT POLE
- PROP. PUBLIC ACCESS EASEMENT
- PROP. UTILITY EASEMENT

PARKING TABLE

ITEM	QUANTITY
EXISTING PARKING SPOTS	125
EXISTING ADA SPOTS	9
REQUIRED ADA SPOTS	4
PROPOSED PARKING SPOTS	81
PROPOSED ADA SPOTS	8

IMPERVIOUS COVER COMPARISON

	PERVIOUS	IMPERVIOUS	TOTAL
EXISTING	15497.11	66628.36	82125.47
PROPOSED	6426.58	75698.89	82125.47
IMPERVIOUS INCREASE		9070.53	

ISSUE FOR CONSTRUCTION






ARCHITECT: SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1

600 S Miltman St.
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION




CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/12	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER


SITE FIRE PLAN

C201






LEGEND	
[Symbol]	PROPOSED ASPHALT PAVEMENT
[Symbol]	PROPOSED STRUCTURAL PAVEMENT
[Symbol]	REF. STRUCTURAL
[Symbol]	PROPOSED 4" CONCRETE SIDEWALK
[Symbol]	PROPOSED BUILDING
[Symbol]	EXISTING PAVEMENT EDGE
[Symbol]	PROPERTY LINE
[Symbol]	EXISTING EASEMENT
[Symbol]	PROPOSED EASEMENT
[Symbol]	EXISTING CONTOURS
[Symbol]	PROPOSED CONTOURS
[Symbol]	EX. PROP. STORM LINE
[Symbol]	EX. PROP. WATER LINE
[Symbol]	EX. PROP. SANITARY SEWER LINE
[Symbol]	EXISTING THERMALS
[Symbol]	PROPOSED THERMALS
[Symbol]	EX. PROP. GAS LINE
[Symbol]	EX. PROP. DATA/TELECOM
[Symbol]	EX. PROP. UNDERGROUND ELECTRIC
[Symbol]	EX. PROP. FIBER OPTIC
[Symbol]	EX. PROP. OVERHEAD ELECTRIC
[Symbol]	EX. PROP. FIRE HYDRANT
[Symbol]	EX. PROP. WATER METER
[Symbol]	EX. PROP. GATE VALVE
[Symbol]	EX. IRRIGATION CONTROL VALVE
[Symbol]	PROP. FIRE DEPARTMENT CONNECTION
[Symbol]	PROP. POST INDICATOR VALVE
[Symbol]	PROP. HOSE LAY
[Symbol]	EX. PROP. SANITARY SEWER MANHOLE
[Symbol]	EX. PROP. SANITARY SEWER CLEANOUT
[Symbol]	EX. STORM SEWER MANHOLE
[Symbol]	PROP. STORM SEWER CURB INLET
[Symbol]	EX. PROP. LIGHT POLE
[Symbol]	PAE PROPOSED PUBLIC ACCESS EASEMENT
[Symbol]	PUE PROPOSED UTILITY EASEMENT

FIRE PROTECTION INFO			
OWNER:	ST. PHILLIPS COLLEGE		
SITE AREA (SF)	21,863		
NO. OF STORIES	1		
PROPOSED BUILDING	TOTAL GSF	HEIGHT	TYPE
	26,114	38 ft	IIB
TOTAL REQUIRED FLOW (GPM)	3,500		
BUILDING SPRINKLER SYSTEM:	YES		
REDUCTION DUE TO SPRINKLERS:	75%		
FINAL REQUIRED FIRE FLOW	875		
AVAILABLE FLOW @ 20 PSI (GPM)	940		



ISSUE FOR CONSTRUCTION

Sheet Grids Template
2400
FOR BLUEBERRY LABELING.COR.





ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	DESIGN
T. J. GESSNER 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	LANDSCAPE ARCHITECTURE
LUNY & HARRIS ENGINEERING 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	ENGINEERING
LUNY & HARRIS ENGINEERING 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	PROFESSIONAL
LUNY & HARRIS ENGINEERING 210-829-0123 P 210-829-0578 F TX Firm BR 1608	

WFAC Black Box Addition PKG 1

600 S Miltman St.
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/12	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER

EXISTING CONDITIONS & DEMO PLAN

C300

CHECKED BY:
SH & AL
DRAWN BY:
JC

ISSUE FOR CONSTRUCTION



CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA ARCHITECTS
12500 N. LOOP WEST SUITE 100 DALLAS, TEXAS 75244 214-343-9999 TX Firm BR 1608	
LANDSCAPE ARCHITECT	LANDSCAPE ARCHITECTS
11111 W. LOOP WEST SUITE 100 DALLAS, TEXAS 75244 214-343-9999 TX Firm BR 1608	
ENGINEER	LUNDY & HARRIS ENGINEERING
11111 W. LOOP WEST SUITE 100 DALLAS, TEXAS 75244 214-343-9999 TX Firm BR 1608	
PROFESSOR OF PRACTICE	MEAD & METCALF
11111 W. LOOP WEST SUITE 100 DALLAS, TEXAS 75244 214-343-9999 TX Firm BR 1608	

LEGEND

- 340 --- EXISTING CONTOURS
- (340) PROPOSED CONTOURS
- PROPERTY LINE
- PROPOSED SWALE WITH DIRECTION OF FLOW ARROWS
- GRADE BREAK
- BR PROPOSED FINISHED GRADE AT BOTTOM OF RAMP
- BS PROPOSED FINISHED GRADE AT BOTTOM OF STAIR
- BW PROPOSED FINISHED GRADE AT BASE OF WALL
- FG PROPOSED FINISHED GRADE ELEVATION
- FL PROPOSED FLOWLINE ELEVATION
- G PROPOSED GUTTER FLOWLINE ELEVATION
- GB PROPOSED GRADE BREAK
- JB PROPOSED TOP OF JUNCTION BOX ELEVATION
- ME @ SW MATCH EXISTING SIDEWALK ELEVATION
- ME @ TC MATCH EXISTING TOP OF CURB ELEVATION
- ME @ TP MATCH EXISTING TOP OF PAVEMENT ELEVATION
- SW PROPOSED TOP OF PAVEMENT AT SIDEWALK ELEVATION
- TC PROPOSED TOP OF CURB ELEVATION
- TG PROPOSED TOP OF GRATE ELEVATION
- TP PROPOSED TOP OF PAVEMENT ELEVATION
- TR PROPOSED TOP OF RAMP ELEVATION
- TW PROPOSED TOP OF WALL ELEVATION
- TMS PROPOSED TOP MUD SLAB
- BMS PROPOSED BOTTOM OF MUD SLAB




CLIENT		Alamo Colleges
DATE	2024/06/12	PROJECT NUMBER
DRAWING HISTORY		230462
No.	Description	Date



ISSUE FOR CONSTRUCTION
BUILDING NUMBER

GRADING PLAN

C400



ISSUE FOR CONSTRUCTION



LEGEND




---	340	EXISTING CONTOURS
---	(340)	PROPOSED CONTOURS
---	---	PROPERTY LINE
---	---	PROPOSED SWALE WITH DIRECTION OF FLOW ARROWS
---	---	GRADE BREAK
BR	---	PROPOSED FINISHED GRADE AT BOTTOM OF RAMP
BS	---	PROPOSED FINISHED GRADE AT BOTTOM OF STAIR
BW	---	PROPOSED FINISHED GRADE AT BASE OF WALL
FG	---	PROPOSED FINISHED GRADE ELEVATION
FL	---	PROPOSED FLOWLINE ELEVATION
G	---	PROPOSED GUTTER FLOWLINE ELEVATION
GB	---	PROPOSED GRADE BREAK
JB	---	PROPOSED TOP OF JUNCTION BOX ELEVATION
ME @ SW	---	MATCH EXISTING SIDEWALK ELEVATION
ME @ TC	---	MATCH EXISTING TOP OF CURB ELEVATION
ME @ TP	---	MATCH EXISTING TOP OF PAVEMENT ELEVATION
SW	---	PROPOSED TOP OF PAVEMENT AT SIDEWALK ELEVATION
TC	---	PROPOSED TOP OF CURB ELEVATION
TG	---	PROPOSED TOP OF GRATE ELEVATION
TP	---	PROPOSED TOP OF PAVEMENT ELEVATION
TR	---	PROPOSED TOP OF RAMP ELEVATION
TW	---	PROPOSED TOP OF WALL ELEVATION
TMS	---	PROPOSED TOP MUD SLAB
BMS	---	PROPOSED BOTTOM OF MUD SLAB



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
2101 BRUNNEN CELEBRITY LANDSCAPE DESIGN GROUP 113140-0020 SAN ANTONIO, TX 78203 LINDY & TRAVIS ENGINEERING 113140-0020 SAN ANTONIO, TX 78203 T. 210-829-0020 F. 210-829-0020 T. 210-829-0020 T. 210-829-0020	

WFAC Black Box Addition PKG 1

600 S. Mittman St.
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION



BUILDING NUMBER

CRAWLSPACE

C401

ISSUE FOR PERMIT

Sheet Grids Template
Z400
FOR BLUEBAM LABELING.COR.



LEGEND

- DRAINAGE AREA BOUNDARY
- ⊙ A1 DRAINAGE AREA LABEL AND FLOW DIRECTION
- PROPERTY LINE
- - - - - EXISTING CONTOURS
- - - - - PROPOSED CONTOURS
- FLOW PATH



CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1

600 S Milman St.
San Antonio, TX 78203
ISSUE FOR PERMIT



CLIENT Alamo Colleges
DATE 2024/06/12 PROJECT NUMBER 230462

DRAWING HISTORY

No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER

PRE DRAINAGE AREA MAP

C500

Pre AREA A

COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	23001.03	0.53	0.50
Grass Cover	Grass Cover > 75%	0.35	5475.37	0.13	0.04
TOTAL			28476.40	0.65	0.55
				C	0.83

Pre AREA B

COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	38420.17	0.88	0.84
Grass Cover	Grass Cover > 75%	0.35	6070.51	0.14	0.05
TOTAL			44490.68	1.02	0.89
				C	0.87

Pre AREA C

COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	5207.16	0.12	0.11
Grass Cover	Grass Cover > 75%	0.35	3951.23	0.09	0.03
TOTAL			9158.39	0.21	0.15
				C	0.70

PRE DEVELOPMENT PEAK RUNOFF

AREA	SIZE (AC)	C	TC (MIN)	1 YR (CFS)	5 YR (CFS)	25 YR (CFS)	100 YR (CFS)
A	0.65	0.83	5.0	2.9	4.2	5.9	7.4
B	1.02	0.87	5.0	4.7	7.0	9.7	12.2
C	0.21	0.70	9.0	0.7	1.0	1.3	1.6

Atlas 14 Rainfall Intensity (in/hr)

Time (minutes)	1 - YEAR	5 - YEAR	25 - YEAR	100 - YEAR
5	5.29	7.88	11.00	13.79
6	5.07	7.45	10.43	13.08
7	4.86	7.11	9.95	12.49
8	4.64	6.81	9.54	11.97
9	4.43	6.54	9.17	11.49
10	4.21	6.30	8.82	11.05



Pre

Area A		Area B		Area C	
C	0.83	C	0.87	C	0.70
Area (ac)	0.65	Area (ac)	1.02	Area (ac)	0.21
Flow Length (ft)	315.12	Flow Length (ft)	479.97	Flow Length (ft)	70.70
SCS Sheet Flow (ft)	68.20	SCS Sheet Flow (ft)	85.32	SCS Sheet Flow (ft)	47.40
Slope (%)	1.02	Slope (%)	1.28	Slope (%)	1.78
Manning's Roughness	0.013	Manning's Roughness	0.013	Manning's Roughness	0.300
Flow Time (min)	1.06	Flow Time (min)	1.16	Flow Time (min)	8.91
SCS Shallow Concentrated Flow (ft)	246.92	SCS Shallow Concentrated Flow (ft)	180.17	SCS Sheet Flow (ft)	23.30
PAVEMENT		PAVEMENT		Slope (%)	1.57
Slope (%)	1.00	Slope (%)	0.86	Manning's Roughness	0.011
Velocity (ft/s)	2.03	Velocity (ft/s)	1.89	Flow Time (min)	0.38
Flow Time (min)	2.03	Flow Time (min)	1.59	Time of Concentration (min)	9.00
Time of Concentration (min)	3.09	SCS Channel Flow (ft)	153.60	*COSA requires min TOC of 5 min*	
COSA requires min TOC of 5 min		Slope (%)	0.21		
		Manning's Roughness	0.012		
		Velocity (ft/s)	2.95		
		Flow Time (min)	0.85		
		SCS Channel Flow (ft)	60.88		
		Slope (%)	1.79		
		Manning's Roughness	0.011		
		Velocity (ft/s)	6.50		
		Flow Time (min)	0.10		
		Time of Concentration (min)	3.70		
		COSA requires min TOC of 5 min			

CHECKED BY: SH & AL
DRAWN BY: JC

ISSUE FOR PERMIT

Sheet Grids Template
Z400
FOR BLUEBAM LABELING.COR.



LEGEND


- DRAINAGE AREA BOUNDARY
- ⊙ A1 DRAINAGE AREA LABEL AND FLOW DIRECTION
- PROPERTY LINE
- - - - - EXISTING CONTOURS
- PROPOSED CONTOURS
- FLOW PATH

Required Storage	
Storm Event	Required Storage (ft ³)
1 - Year	2037.00
5 - Year	2784.00
25 - Year	3698.00
100 - Year	4549.00



ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1
600 S Milburn St.
San Antonio, TX 78203
ISSUE FOR PERMIT



CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
2024/06/12		

No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER

POST DRAINAGE AREA MAP

C501

POST AREA A					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	2700.94	0.06	0.06
Grass Cover	Grass Cover > 75%	0.35	54.6	0.00	0.00
TOTAL			2755.54	0.06	0.06
			C		0.94

POST AREA B					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	67228.61	1.54	1.47
Grass Cover	Grass Cover > 75%	0.35	4672.06	0.11	0.04
TOTAL			71900.67	1.65	1.50
			C		0.91

POST AREA C					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	5769.34	0.13	0.13
Grass Cover	Grass Cover > 75%	0.35	1699.92	0.04	0.01
TOTAL			7469.26	0.17	0.14
			C		0.81

POST DEVELOPMENT PEAK RUNOFF							
AREA	SIZE (AC)	C	TC (MIN)	1 YR (CFS)	5 YR (CFS)	25 YR (CFS)	100 YR (CFS)
A	0.06	0.94	5.0	0.3	0.4	0.6	0.8
B	1.65	0.91	5.0	8.2	12.2	16.9	21.2
C	0.17	0.81	8.0	0.6	0.9	1.3	1.6



Time (minutes)	Atlas 14 Rainfall Intensity (in/hr)			
	1 - YEAR	5 - YEAR	25 - YEAR	100 - YEAR
5	5.29	7.88	11.00	13.79
6	5.07	7.45	10.43	13.08
7	4.86	7.11	9.95	12.49
8	4.64	6.81	9.54	11.97
9	4.43	6.54	9.17	11.49
10	4.21	6.30	8.82	11.05

Post			
Area A	Area B	Area C	
C	0.94	C	0.91
Area (ac)	0.06	Area (ac)	1.65
Flow Length (ft)	29.10	Flow Length (ft)	416.77
SCS Sheet Flow (ft)	29.10	SCS Sheet Flow (ft)	85.32
Slope (%)	0.99	Slope (%)	1.28
Manning's Roughness	0.011	Manning's Roughness	0.013
Flow Time (min)	0.54	Flow Time (min)	1.32
Time of Concentration (min)	0.54	SCS Shallow Concentrated Flow (ft)	81.23
COSA requires min TOC of 5 min			
PAVEMENT			
Slope (%)	0.65	SCS Sheet Flow (ft)	32.46
Velocity (ft/s)	1.64	Slope (%)	2.55
Flow Time (min)	0.83	Manning's Roughness	0.011
SCS Channel Flow (ft)	224.55	Flow Time (min)	0.40
Slope (%)	0.50	Time of Concentration (min)	8.00
Manning's Roughness	0.011	*COSA requires min TOC of 5 min*	
Velocity (ft/s)	5.00		
Flow Time (min)	0.74		
SCS Channel Flow (ft)	25.67		
Slope (%)	0.50		
Manning's Roughness	0.011		
Velocity (ft/s)	7.00		
Flow Time (min)	0.06		
Time of Concentration (min)	2.95		
COSA requires min TOC of 5 min			


CHECKED BY: SH & AL
DRAWN BY: JC

Sheet Grids Template
FOR BLUEBAM LABELING CORR.


ISSUE FOR CONSTRUCTION



NOTE:
CONTRACTOR TO FIELD VERIFY EXISTING
UTILITY INVERTS PRIOR TO CONSTRUCTION



EL-02
SCALE: 1"=20' H, 1"=5' V




FO-01
SCALE: 1"=20' H, 1"=5' V

LEGEND	
[Symbol]	PROPOSED ASPHALT PAVEMENT
[Symbol]	PROPOSED STRUCTURAL PAVEMENT
[Symbol]	REF. STRUCTURAL
[Symbol]	PROPOSED 4" CONCRETE SIDEWALK
[Symbol]	PROPOSED BUILDING
[Symbol]	EXISTING PAVEMENT EDGE
[Symbol]	PROPERTY LINE
[Symbol]	EXISTING EASEMENT
[Symbol]	PROPOSED EASEMENT
[Symbol]	EXISTING CONTOURS
[Symbol]	PROPOSED CONTOURS
[Symbol]	EX. PROP. STORM LINE
[Symbol]	EX. PROP. WATER LINE
[Symbol]	EX. PROP. SANITARY SEWER LINE
[Symbol]	EXISTING THERMALS
[Symbol]	PROPOSED THERMALS
[Symbol]	EX. PROP. GAS LINE
[Symbol]	EX. PROP. DATA/TELECOM
[Symbol]	EX. PROP. UNDERGROUND ELECTRIC
[Symbol]	EX. PROP. FIBER OPTIC
[Symbol]	EX. PROP. OVERHEAD ELECTRIC
[Symbol]	EX. PROP. FIRE HYDRANT
[Symbol]	EX. PROP. WATER METER
[Symbol]	EX. PROP. GATE VALVE
[Symbol]	EX. IRRIGATION CONTROL VALVE
[Symbol]	PROP. FIRE DEPARTMENT CONNECTION
[Symbol]	PROP. POST INDICATOR VALVE
[Symbol]	PROP. HOSE LAY
[Symbol]	EX. PROP. SANITARY SEWER MANHOLE
[Symbol]	EX. PROP. SANITARY SEWER CLEANOUT
[Symbol]	EX. STORM SEWER MANHOLE
[Symbol]	PROP. STORM SEWER CURB INLET
[Symbol]	EX. PROP. LIGHT POLE
[Symbol]	PROPOSED PUBLIC ACCESS EASEMENT
[Symbol]	PROPOSED UTILITY EASEMENT



ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1



STATE OF TEXAS
ANDREW A. LANGE
118770
06/14/2024

DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER


ELEC. & COMMS
PLAN & PROFILES

C700

CHECKED BY: SH & AL
DRAWN BY: JC




Sheet Grids Template
 Z:400
 FOR BLUEBAM LABELING CORR.

ISSUE FOR PERMIT



ARCHITECT	PBK Architects, Inc.
PROJECT	WFAC Black Box Addition
DATE	08/05/2024
SCALE	1"=20'
PROJECT NO.	230462
DATE	08/05/2024
DESCRIPTION	ADDENDUM 1

SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	SAN ANTONIO 600 S Alhambra St. San Antonio, TX 78203 ISSUE FOR PERMIT
---	--




CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT



BUILDING NUMBER

STORM PLAN

C800




CHECKED BY: SH & AL
 DRAWN BY: JC




ST-1
SCALE: 1"=20' H, 1"=5' V


NOTE:
CONTRACTOR TO FIELD VERIFY EXISTING
UTILITY INVERTS PRIOR TO CONSTRUCTION




ST-2
SCALE: 1"=20' H, 1"=5' V




ST-3
SCALE: 1"=20' H, 1"=5' V



ST-5
SCALE: 1"=20' H, 1"=5' V



ST-4
SCALE: 1"=20' H, 1"=5' V



ST-6
SCALE: 1"=20' H, 1"=5' V






ARCHITECT	PBK Architects, Inc.
601 N.W. Loop 410, Suite 400	San Antonio, TX 78216
210-829-0123 P	210-829-0578 F
TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
1301 BRIDGE	
DESIGN	
LANDSCAPE	
POST AND DESIGN	
1131 ALAMO	
TRUCKEE, CA	
UNIVERSITY ENGINEERING	
1000 UNIVERSITY	
DRYDEN, CA	
PROFESSIONAL	
1300 SOUTH	
1300 SOUTH	
1300 SOUTH	
1300 SOUTH	

WFAC Black Box Addition PKG 1

600 S Milam St.
San Antonio, TX 78203

ISSUE FOR PERMIT



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/12	230462	
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT

BUILDING NUMBER

STORM PROFILES

C801

ISSUE FOR PERMIT



Sheet Grids Template
Z400
FOR BLUEBAM LABELING.COR.

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
DESIGNER	BA & ARCHITECTS
LANDSCAPE	BA & ARCHITECTS
STRUCTURAL	BA & ARCHITECTS
MECHANICAL/ELECTRICAL/PLUMBING	BA & ARCHITECTS
TRAFFIC	BA & ARCHITECTS
PROVIDER	BA & ARCHITECTS
MEASURER	BA & ARCHITECTS
DATE	08/05/2024

WFAC Black Box Addition PKG 1





CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER

DETENTION PLAN



C802



UNDERGROUND DETENTION OUTLET STRUCTURE
N.T.S.
NOTES:
1. ALL REINFORCEMENT BARS TO HAVE 2\"/>


CHECKED BY: SH & AL
DRAWN BY: JC

ISSUE FOR CONSTRUCTION



NOTE:
CONTRACTOR TO FIELD VERIFY EXISTING
UTILITY INVERTS PRIOR TO CONSTRUCTION

LEGEND	
	PROPOSED ASPHALT PAVEMENT
	PROPOSED STRUCTURAL PAVEMENT





SA-1
SCALE: 1"=20' H, 1"=5' V



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA & ARCHITECTS
1301 BRUNNEN CELEBRITY LANDSCAPE DESIGN GROUP 1131 W. 30th SAN ANTONIO, TX 78207 LUNDY & HARRIS ENGINEERING 1131 W. 30th SAN ANTONIO, TX 78207 TRAVIS NEAR POWER SIGNALS 1131 W. 30th SAN ANTONIO, TX 78207	

WFAC Black Box Addition PKG 1





CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER
SANITARY PLAN & PROFILES

C900

ISSUE FOR CONSTRUCTION



LEGEND

	CONSTRUCTION ENTRANCE, INSTALLED PER DETAIL
	PROPERTY LINE
	EXISTING CONTOURS
	PROPOSED CONTOURS
	EXISTING FLOW PATH
	PROPOSED FLOW PATH
	SILT FENCE, INSTALLED PER DETAIL
	PROPOSED DAM EROSION CONTROL, LOG-18"
	PROPOSED ROCK FILTER DAM TYPE 3
	PROP. TREE PROTECTION FENCE
	PROP. TREE PROTECTION FENCE

EROSION CONTROL NOTES:
OWNER INFORMATION: ST PHILLIPS COLLEGE
PROJECT NAME: ST PHILLIPS COLLEGE WATSON FINE ARTS CENTER BLACK BOX ADDITION
PROJECT LOCATION: 600 S MITTMAN ST. SAN ANTONIO, TX 78203

LATITUDE: 29°24'49.57"N
LONGITUDE: 98°27'14.61"W
TOTAL SITE AREA IS: 1.89 ACRES
TOTAL AREA OF SITE EXPECTED TO BE DISTURBED: 1.35 ACRES

EXISTING SITE CONDITIONS
LAND USE: HIGHER EDUCATION
LAND COVER: ~90% IMPERVIOUS
RECEIVING WATERS: SALADO CREEK
SEGMENT NO. OF CLASSIFIED WATER BODY: SALADO CREEK
BASIN NAME: SAN ANTONIO RIVER

SOIL INFORMATION
HYDROLOGIC SOIL GROUP: D

POST DEVELOPED SITE CONDITIONS
LAND USE: HIGHER EDUCATION
ACADEMIC BLDG

NATURE OF ACTIVITIES
ACADEMIC BLDG




- SEQUENCE OF MAJOR ACTIVITIES**
1. INSTALL SILT FENCE AT STOCK PILE AREAS
 2. CLEARING, GRADING, GENERAL CONSTRUCTION SITE
 3. INSTALL FILTER ELEMENTS IMMEDIATELY AFTER DISTURBANCE AND/OR GRADING OPERATIONS.
 4. AFTER ESTABLISHMENT OF GRASS, REMOVE ALL TEMPORARY EROSION CONTROL.
 5. SEED ALL AREAS NOT HAVING PERMANENT GRASS COVERAGE AFTER APPROVAL BY COUNTY INSPECTOR.

- GENERAL EROSION CONTROL NOTES**
1. ALL UTILITIES AND SERVICE LINES SHOWN ARE TAKEN FROM RECORD INFORMATION SUPPLIED BY THE UTILITY OWNER OR HORIZONTALLY LOCATED BY INDEPENDENT LOCATORS. CONTRACTOR IS RESPONSIBLE TO REPORT ANY CONFLICTS BETWEEN PLAN AND ACTUAL CONDITIONS PRIOR TO CONSTRUCTION. OWNER AND ENGINEER SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF INFORMATION OR DATA RELIED ON TO DEPICT UNDERGROUND FACILITIES. CONTRACTOR IS TO CONTACT OWNERS OF ALL UTILITIES AND SERVICE LINES WITHIN THE PROJECT AREA AND NOTIFY OF INTENT AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH FACILITY OWNERS. CONTRACTOR IS TO VERIFY THE EXACT LOCATION AND VERTICAL POSITIONING OF ALL PIPELINES, EXISTING UTILITIES, AND SERVICE LINES WITHIN THE PROJECT AREA WHETHER SHOWN ON THE PLANS OR NOT. AT LEAST 48 HOURS PRIOR TO CONSTRUCTION CONTRACTOR IS TO MAINTAIN STRUCTURAL INTEGRITY OF ALL PIPELINES, ELECTRIC TRANSMISSION POLES AND LINES, PERMANENT AND TEMPORARY UTILITIES. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE DONE TO EXISTING UTILITY FACILITIES, PAVEMENT, ETC. AS A RESULT OF CLEARING/DIRTWORK ACTIVITIES.
 2. CONTRACTOR TO CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION. CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.
 3. ALL DISTURBED AREAS NOT TO BE PAVED ARE TO HAVE ESTABLISHMENT OF GRASS.
 4. ALL SWALE AREAS (BOTTOM WIDTHS & SIDE SLOPES) ARE TO BE PREPARED AND HYDROMULCHED FOR PERMANENT ESTABLISHMENT OF VEGETATION. PRIOR TO HYDROMULCHING OPERATIONS, CONTRACTOR TO REPLACE TOPSOIL TO A DEPTH OF 6". TOPSOIL IS TO BE DISKED TO A DEPTH OF AT LEAST 4" AND LIGHTLY COMPACTED. FINAL GRADES WITH ESTABLISHED VEGETATION SHALL BE AS CALLED OUT ON THE GRADING PLAN.
 5. CONTRACTOR IS TO MAINTAIN EROSION CONTROL AT ALL LOCATIONS OF CONSTRUCTION THROUGHOUT DURATION OF THE PROJECT AND UNTIL VEGETATION IS ESTABLISHED. INSURE SEDIMENT IS NOT TRANSPORTED DOWNSTREAM FROM PROJECT VIA GRAVEL FILTER BAGS AND SILT FENCE INSTALLATIONS. IF EXCESSIVE EROSION IS OBSERVED IN THE FIELD, ADDITIONAL EROSION CONTROLS SHALL BE INSTALLED.
 6. CONTRACTOR SHALL NOT ALLOW SEDIMENT TO ENTER THE DOWNSTREAM CHANNEL. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING OF THE DOWNSTREAM CHANNEL AREAS AND RESTORING TO ORIGINAL CONDITION, INCLUDING ESTABLISHMENT OF REVEGETATION SHOULD CONSTRUCTION SEDIMENT BE FOUND OUTSIDE THE LIMITS OF CONSTRUCTION.
 7. THE CONTRACTOR WILL REMOVE ALL EXCESS SOIL FROM CONSTRUCTION VEHICLES PRIOR TO EXITING THE SITE.
 8. THE CONTRACTOR SHALL UNDERTAKE PROPER METHODS TO REDUCE DUST GENERATION FROM THE SITE.
 9. THE CONTRACTOR MUST COMPLY WITH FEDERAL, STATE, AND LOCAL REGULATIONS REGARDING SEDIMENTS AND EROSION CONTROL.
 10. A COPY OF THIS PLAN MUST BE KEPT AT THE CONSTRUCTION FACILITY DURING THE ENTIRE CONSTRUCTION PERIOD.
 11. ALL FINISHED GRADES ARE TO BE HYDRO-MULCHED, SPOT SODDED OR SEEDED AND WATERED UNTIL GROWTH IS ESTABLISHED.
 12. CONTRACTOR IS RESPONSIBLE TO FILE THE NOTICE OF INTENT AND NOTICE OF TERMINATION WITH AUTHORITY HAVING JURISDICTION.



ARCHITECT	PBK Architects, Inc.
601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA ARCHITECTS
1701 BRUNNEN CELEBRITY LANDSCAPE DESIGN GROUP 1713 BRUNNEN CELEBRITY LUNY & HARRIS ENGINEERING 1713 BRUNNEN CELEBRITY DESIGN 1713 BRUNNEN CELEBRITY DESIGN 1713 BRUNNEN CELEBRITY DESIGN	

WFAC Black Box Addition PKG 1



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/12	230462	
DRAWING HISTORY		
No.	Description	Date


ISSUE FOR CONSTRUCTION
BUILDING NUMBER

EROSION CONTROL


C1100

GENERAL NOTES

1. NEW PIPE TO BE SET FLUSH WITH INSIDE WALL OF STRUCTURE.




GRAOUTED STORM SEWER CONNECTION DETAIL
NTS




PROPOSED MANHOLE ON EXISTING BOX STORM SEWER
NTS

TABLE
SEWER SIZE VS. OPENING

SEWER SIZE (INCHES)	MANHOLE BASE DIAMETER
48"	36"
54"	36"
60"	42"
66" OR GREATER	48"




INTEGRAL CURB & GUTTER
NTS




NOTE: SEE PLAN C.X.X FOR JOINT LOCATIONS

CONCRETE TO ASPHALT J-JOINT
NTS




1 1/2" HMAc PAVEMENT
NTS




NOTE: SIDEWALK EXPANSION JOINTS SHALL BE INSTALLED AS SHOWN ON PLANS

SIDEWALK EXPANSION JOINT
NTS




NOTE: SIDEWALK JOINT SPACING PER LANDSCAPE ARCHITECT OR JOINT PLAN. IF NOT SPECIFIED, SPACING SHALL BE EQUAL TO SIDEWALK WIDTH WITH A MAXIMUM SPACING OF 8-FOOT.

SIDEWALK CONTRACTION JOINT
NTS




EXPANSION JOINT
NTS




NOTES:
1. SUBGRADE STABILIZATION SHALL BE PER GEOTECHNICAL RECOMMENDATIONS AND LIME/CEMENT SERIES BASED ON ACTUAL SUBGRADE CONDITIONS.
2. SAW CUT OPERATIONS SHALL BEGIN AS SOON AS POSSIBLE AFTER CONCRETE PLACEMENT.
3. SEAL ALL EXPANSION JOINTS WITH SEAL CAP AND CONTROL JOINTS WITH SELF LEVELING JOINT SEALANT MATERIAL PER SPECIFICATIONS. USE SELF LEVELING JOINT SEALANT ADJACENT TO EXISTING PAVEMENT.

SIDEWALK SECTION
NTS




NOTES:
1. SEE PLAN FOR JOINT SPACING, COMPRESSIVE STRENGTH, PAVEMENT THICKNESS, AND REINFORCING.
2. DEPTH OF STABILIZATION SHALL BE A MINIMUM OF 6 INCHES OR BASED ON GEOTECHNICAL RECOMMENDATIONS SUBGRADE CONDITIONS.
3. SUBGRADE STABILIZATION SHALL BE PER GEOTECHNICAL RECOMMENDATIONS AND LIME/CEMENT SERIES BASED ON ACTUAL SUBGRADE CONDITIONS.

CONCRETE PAVEMENT
NTS



NOTES:
1. SEE PLANS FOR JOINT SPACING, COMPRESSIVE STRENGTH, PAVEMENT THICKNESS, AND REINFORCING.
2. SAW CUT OPERATIONS SHALL BEGIN AS SOON AS POSSIBLE AFTER CONCRETE PLACEMENT.
3. SEAL ALL JOINTS WITH SELF LEVELING JOINT SEALANT MATERIAL PER SPECIFICATIONS.

CONTROL JOINT
NTS




A. SATISFACTORY SOILS
MATERIAL EXCAVATED FROM THE DITCH, (WHICH IS FREE OF ROCKS, LUMPS, CLODS, OR DEBRIS LARGER THAN TWO (2) INCHES IN THE LARGEST DIMENSION), COMPACTED TO A MINIMUM OF 90% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT MOISTURE CONTENT WITHIN OPTIMUM TO 2% OF OPTIMUM UNDER NON-STRUCTURAL AREAS (IE. YARDS, PASTURES, EASEMENTS) AND TO A MINIMUM OF 90% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN OPTIMUM TO 2% OF OPTIMUM UNDER NEW STREET AND PAVEMENT AREAS.

B. BANK RUN SAND
GRANULAR MATERIAL FREE OF DETRIMENTAL QUANTITIES OF CLAY, DEBRIS, OR ORGANIC MATERIAL. REFERENCE SPECIFICATION FOR REQUIREMENTS.

C. CEMENT STABILIZED SAND
MATERIALS SHALL BE TYPE PORTLAND CEMENT CONFORMING TO ASTM C150 AND CLEAN DURABLE SAND MEETING GRADING REQUIREMENTS FOR FINE AGGREGATES OF ASTM C33. THE CEMENT STABILIZED SAND SHALL HAVE A MINIMUM OF 10% CEMENT PER CUBIC YARD OF CEMENT STABILIZED SAND MIXTURE, BASED ON LOOSE DRY WEIGHT VOLUME (AT LEAST 2.5 SACKS OF CEMENT PER CUBIC YARD OF MIXTURE). COMPACT MIX TO 90% OF ASTM D698 WITH A MOISTURE CONTENT BETWEEN .2% TO 2% ABOVE OPTIMUM.

D. PAVEMENT SUBGRADE
REFERENCE PAVEMENT SECTION DETAIL AND SPECIFICATION FOR MATERIALS AND DEPTHS.



A. SELECT MATERIAL
EXISTING GRADE
PLACE METAL DETECTOR TAPE AT A MINIMUM OF 24" ABOVE TOP OF PIPE

B. BANK RUN SAND
UNDISTURBED SOIL

C. CEMENT STABILIZED SAND
UNDISTURBED SOIL

D. PAVEMENT BASE AND SUBGRADE PER DETAILS & NOTES
C. CEMENT STABILIZED SAND
B. BANK RUN SAND
UNDISTURBED SOIL


GENERAL NOTES:
ALL AREAS WHERE EXISTING VEGETATION AND GRASS COVER HAVE BEEN BARED BY CONSTRUCTION SHALL BE ADEQUATELY BLOCK SOODED OR HYDROMULCHED AND WATERED UNTIL GROWTH IS ESTABLISHED. IN DEVELOPED AREAS WHERE GRASS IS PRESENT, BLOCK SOO WILL BE REQUIRED. BARED AREAS SHALL BE SEEDED OR SOODED WITHIN 14 CALENDAR DAYS OF LAST DISTURBANCE.

APPROVED EROSION CONTROL MEASURES MUST BE INSTALLED DURING THE ENTIRE TIME THAT EARTH HAS BEEN BARED BY CONSTRUCTION AND SHALL STAY IN PLACE UNTIL ACCEPTABLE VEGETATIVE GROWTH IS ESTABLISHED AFTER CONSTRUCTION IS COMPLETE AND THEN REMOVED BY CONTRACTOR.

ALL EROSION CONTROL MEASURES SHOULD BE CLEANED OF SILT AFTER EVERY RAIN.

ESTABLISHMENT OF VEGETATION MAY BE A WARRANTY ITEM


BEDDING AND TRENCH FOR HDPE PIPE
NTS



SINGLE GRATE INLET
NTS



STORM SEWER JUNCTION BOX
NTS






GRATE INLET
NTS

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION. CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT: SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-0578 F
TX Firm BR 1608
ARCHITECT: BA & ARCHITECTS
210-820-0123 P
210-829-0578 F
TX Firm BR 1608
ARCHITECT: LUNBY & HARRIS ENGINEERING
210-820-0123 P
210-829-0578 F
TX Firm BR 1608
ARCHITECT: NEAR NORTH CONSULTANTS
210-820-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1
600 S Milam St.
San Antonio, TX 78203
ISSUE FOR PERMIT



CLIENT: Alamo Colleges
DATE: 2024/06/12 PROJECT NUMBER: 230462


No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER


DETAILS
C1200

GENERAL NOTES:

- FINELY DIVIDED EARTH FREE OF ROCK, LUMPS AND CLODS EXCEEDING 6" SHALL BE PLACED BY HAND, AND COMPACTED AROUND THE CAST IRON PIPE TO A DEPTH OF 12" OVER THE TOP OF THE PIPE BEFORE BACKFILL IS BEGUN BY ANY MECHANICAL EQUIPMENT.
- ALL CONCRETE BLOCKING SHALL BE - 28 DAY CONCRETE STRENGTH = 2000psi.
- ALL THRUST BLOCKING SHALL PROVIDE A MINIMUM OF 2 SQUARE FEET OF BEARING AREA OF CONCRETE ON UNDISTURBED SOIL, OR AS DIRECTED BY THE ENGINEER.
- WATER MAINS WILL NOT BE FULLY PRESSURIZED UNTIL CONCRETE HAS REACHED 7 DAY STRENGTH.
- ALL PIPE WILL BE LAID SO AS THE ENTIRE BARRELL WILL HAVE FULL BEARING ON THE FINE GRADED TRENCH BOTTOM. BELL HOLES SHALL BE CUT FOR EACH BELL AND FIRE HYDRANT.
- ALL FITTINGS SHALL BE MECHANICAL JOINTS UNLESS OTHERWISE DIRECTED.
- HYDRANTS SHALL BE LOCATED NO CLOSER THAN 3 FEET MEASURED FROM THE BACK OF CURB TO THE FACE OF THE STEAMER ON THE FIRE HYDRANT.



STANDARD FIRE HYDRANT ASSEMBLY
NTS



BEDDING AND TRENCH FOR REINFORCED CONCRETE PIPE
NTS


- A. SATISFACTORY SOILS**
MATERIAL EXCAVATED FROM THE DITCH, (WHICH IS FREE OF ROCKS, LUMPS, CLODS, OR DEBRIS LARGER THAN TWO (2) INCHES IN THE LARGEST DIMENSION), COMPACTED TO A MINIMUM OF 95% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN -2% TO 2% ABOVE OPTIMUM UNDER NON-STRUCTURAL AREAS (IE., YARDS, PASTURES, EASEMENTS) AND TO A MINIMUM OF 98% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN -2% TO 2% ABOVE OPTIMUM UNDER PAVED AREAS.
- B. CEMENT STABILIZED SAND**
MATERIALS SHALL BE TYPE I PORTLAND CEMENT CONFORMING TO ASTM C150 AND CLEAN DURABLE SAND MEETING GRADING REQUIREMENTS FOR FINE AGGREGATES OF ASTM C33. THE CEMENT STABILIZED SAND SHALL HAVE A MINIMUM OF 10% CEMENT PER CUBIC YARD OF CEMENT STABILIZED SAND MIXTURE, BASED ON LOOSE DRY WEIGHT VOLUME (AT LEAST 2 SACKS OF CEMENT PER CUBIC YARD OF MIXTURE), COMPACT MIX TO 95% OF ASTM D558 WITH A MOISTURE CONTENT BETWEEN -2% TO 2% ABOVE OPTIMUM.
- C. PAVEMENT SUBGRADE**
REFERENCE PAVEMENT SECTION DETAIL AND SPECIFICATION FOR MATERIALS AND DEPTHS.

GENERAL NOTES:
ALL AREAS WHERE EXISTING VEGETATION AND GRASS COVER HAVE BEEN BARED BY CONSTRUCTION SHALL BE ADEQUATELY BLOC SODDED OR HYDROMULCHED AND WATERED UNTIL GROWTH IS ESTABLISHED. IN DEVELOPED AREAS WHERE GRASS IS PRESENT, BLOC SOD WILL BE REQUIRED. BARED AREAS SHALL BE SEED OR SODDED WITHIN 14 CALENDAR DAYS OF LAST DISTURBANCE.


APPROVED EROSION CONTROL MEASURES MUST BE INSTALLED DURING THE ENTIRE TIME THAT EARTH HAS BEEN BARED BY CONSTRUCTION AND SHALL STAY IN PLACE UNTIL ACCEPTABLE VEGETATIVE GROWTH IS ESTABLISHED AFTER CONSTRUCTION IS COMPLETE AND THEN REMOVED BY CONTRACTOR.

ALL EROSION CONTROL MEASURES SHOULD BE CLEANED OF SILT AFTER EVERY RAIN.


ESTABLISHMENT OF VEGETATION MAY BE A WARRANTY ITEM




VIEW A-A




SILT CONTROL FENCE
NTS




CONSTRUCTION ENTRANCE/EXIT
NTS



STANDARD MANHOLE TIE-IN
NTS




PLAN




SECTION A-A

PROPERTY OF SAN ANTONIO WATER SYSTEM SAN ANTONIO, TEXAS	6" TURBINE METER INSTALLATION	APPROVED March 2008	REVISED AUG 2019
		DD-824-09	
		SHEET 2 OF 2	



STORM DRAIN INLET PROTECTION
NTS






ADA PARKING SIGN
NTS

- NOTE:**
- 1" DIA "STARTER HOLES SHALL BE DRILLED THROUGH WALL OF EXISTING MANHOLE SPACED 3" APART CENTER TO CENTER. AFTER "STARTER" HOLES HAVE BEEN INSTALLED AND APPROVED BY A CITY INSPECTOR, THE CONTRACTOR SHALL BEGIN REMOVING THE CONCRETE INSIDE THE PERIPHERAL "STARTER" HOLES. CONCRETE SHALL BE REMOVED WITH PNEUMATIC HAND TOOLS.
 - THE NUMBER OF REBAR DOWELS SHALL VARY WITH SIZE OF OPENING. REBAR SHALL NOT BE SPACED MORE THAN 12" OC.
 - WATERSTOP SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURERS REQUIREMENTS.
 - CONCRETE SHALL BE 3,000 P.S.I.

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA & ARCHITECTS
DESIGNER	BA & ARCHITECTS
LANDSCAPE ARCHITECT	BA & ARCHITECTS
ENGINEER	BA & ARCHITECTS
INSPECTOR	BA & ARCHITECTS
CONTRACTOR	BA & ARCHITECTS
GENERAL CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS
STEEL ERECTOR	BA & ARCHITECTS
GLASS CONTRACTOR	BA & ARCHITECTS
MECHANICAL CONTRACTOR	BA & ARCHITECTS
ELECTRICAL CONTRACTOR	BA & ARCHITECTS
PLUMBING CONTRACTOR	BA & ARCHITECTS
ROOFING CONTRACTOR	BA & ARCHITECTS
PAVING CONTRACTOR	BA & ARCHITECTS
CONCRETE CONTRACTOR	BA & ARCHITECTS
IRONWORK CONTRACTOR	BA & ARCHITECTS



REINFORCING BAR LAP SPlice TABLE (MASONRY), (BEAMS AND COLUMNS), (SLABS AND WALLS). Includes tables for bar size, position, and lap class.

COLUMN SCHEDULE table with columns for MARK, SECT., TOP CONN., BASE PLATE, ANCHORS, SECT., and REMARKS.



Project information including architect (PBK Architects), engineer (Lundy & Franke Engineering), key plan, contractor note, and issue for construction details.




ARCHITECT SAN ANTONIO PBK Architects, Inc. 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216

ENGINEERING LUNDY & FRANKE ENGINEERING 568 HEIMER ROAD San Antonio, Texas 78232

WFCAC Black Box Addition PKG 1 1801 Marlin Luther King Dr. San Antonio, TX 78203

ALAMO COLLEGES ST. PHILLIP'S COLLEGE



SHAWN J. FRANKE LICENSED PROFESSIONAL ENGINEER

DRAWING HISTORY table with columns for No., Description, and Date.

ISSUE FOR CONSTRUCTION BUILDING NUMBER AB

DEFERRED SUBMITTALS				
BUILDING CONSTRUCTION	YES	NO	DESCRIPTION	
STEEL		X	-	
CONCRETE		X	-	
WOOD		X	-	

DEFERRED SUBMITTALS				
BUILDING CONSTRUCTION	YES	NO	DESCRIPTION	
STEEL		X	-	
CONCRETE		X	-	
WOOD		X	-	

DEFERRED SUBMITTALS				
BUILDING CONSTRUCTION	YES	NO	DESCRIPTION	
STEEL		X	-	
CONCRETE		X	-	
WOOD		X	-	

6. MASONRY CONSTRUCTION				
EMPIRICALLY DESIGNED MASONRY - GLASS UNIT MASONRY, AND MASONRY VENEER IN NON-ESSENTIAL FACILITIES.	SPECIAL INSPECTIONS NOT REQUIRED PER 1704.5.1		IBC 1705.4	
LEVEL 1 INSPECTION:	ENGINEERED MASONRY IN NON-ESSENTIAL FACILITIES AND EMPERICALLY DESIGNED MASONRY IN ESSENTIAL FACILITIES.	IBC 1705.4		QUALIFICATIONS BASED ON ASTM C1093
A. AS MASONRY CONSTRUCTION BEGINS, THE FOLLOWING SHALL BE VERIFIED TO ENSURE COMPLIANCE:	<ul style="list-style-type: none"> 1. PROPORTIONS OF SITE-PREPARED MORTAR. 2. CONSTRUCTION OF MORTAR JOINTS. 3. LOCATION OF REINFORCEMENT AND CONNECTORS. 4. PRESTRESSING TECHNIQUE 5. GRADE AND SIZE OF PRESTRESSING TENDONS AND ANCHORAGES. 			
B. THE INSPECTION PROGRAM SHALL VERIFY:	<ul style="list-style-type: none"> 1. SIZE AND LOCATION OF STRUCTURAL ELEMENTS. 2. TYPE, SIZE AND LOCATION OF ANCHORS, INCLUDING OTHER DETAILS OF ANCHORAGE OF MASONRY TO STRUCTURAL MEMBERS, FRAMES, OR OTHER CONSTRUCTION. 3. SPECIFIED SIZE, GRADE AND TYPE OF REINFORCEMENT. 4. WELDING OF REINFORCING BARS. 5. PROTECTION OF MASONRY DURING COLD WEATHER (TEMPERATURE BELOW 40 DEGREES F) OR HOT WEATHER (TEMPERATURE ABOVE 90 DEGREES F). 6. APPLICATION AND MEASUREMENT OF PRESTRESSING FORCE. 			
C. PRIOR TO GROUTING, THE FOLLOWING SHALL BE VERIFIED TO ENSURE COMPLIANCE:	<ul style="list-style-type: none"> 1. GROUT SPACE IS CLEAN. 2. PLACEMENT OF REINFORCEMENT AND CONNECTORS AND PRESTRESSING TENDONS AND ANCHORAGES. 3. PROPORTIONS OF SITE-PREPARED GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS. 4. CONSTRUCTION OF MORTAR JOINTS. 			
D. GROUT PLACEMENT	<ul style="list-style-type: none"> 1. VERIFY COMPLIANCE WITH CODE AND CONSTRUCTION DOCUMENTS PROVISIONS. 2. GROUTING OF PRESTRESSING BONDED TENDONS. 			QUALIFICATIONS BASED ON C1093
E. PREPARATION OF ANY AT THE COVERED GROUT SPECIMENS, MORTAR SPECIMENS AND/OR PRISMS SHALL BE OBSERVED.	<ul style="list-style-type: none"> 1. VERIFY COMPLIANCE WITH CODE AND CONSTRUCTION DOCUMENTS PROVISIONS. 			QUALIFICATIONS BASED ON C1093
F. COMPLIANCE WITH REQUIRED INSPECTION PROVISIONS OF THE CONSTRUCTION DOCUMENTS AND THE APPROVED SUBMITTALS SHALL BE VERIFIED.	<ul style="list-style-type: none"> 1. VERIFY COMPLIANCE WITH CODE AND CONSTRUCTION DOCUMENTS PROVISIONS. 			QUALIFICATIONS BASED ON C1093
G. TESTING OF GROUT SPECIMENS, MORTAR SPECIMENS AND/OR PRISMS.	<ul style="list-style-type: none"> 1. TEST ONE SET OF MORTAR CUBES PER 2000 sq OR PORTION THEREOF. 2. TEST ONE SET OF GROUT CYLINDERS PER 2000 sq OR PORTION THEREOF. 3. TEST ONE PRISM PER 6000 sq OR PORTION THEREOF. (SUBMITTED PRISM WILL BE ACCEPTABLE FOR FIRST PRISM TEST). 			QUALIFICATIONS BASED ON C1093
LEVEL 1 INSPECTION CONT.:	ENGINEERED MASONRY IN NON-ESSENTIAL FACILITIES AND EMPERICALLY DESIGNED MASONRY IN ESSENTIAL FACILITIES.	IBC 1704.5.1, IBC 1704.5.2		QUALIFICATIONS BASED ON ASTM C1093
H. POST INSTALLED REINFORCING & ANCHORS (EXPANSION ANCHORS, SCREW ANCHORS ADHESIVE ANCHORS, ECT.).	THE SPECIAL INSPECTOR SHALL BE ON THE JOB SITE CONTINUOUSLY DURING ANCHOR INSTALLATION TO VERIFY ANCHOR TYPE, ANCHOR DIMENSIONS, MASONRY TYPE AND COMPRESSION STRENGTH. PRE-DRILLED HOLE DIMENSIONS ANCHOR SPACING, EDGE DISTANCES, MASONRY THICKNESS AND ANCHOR EMBEDMENT.	ACI 318 APPENDIX D-CH. D.9.1		QUALIFICATIONS BASED ON ASTM E829 & ASTM C1077 OR CERTIFIED MANUFACTURER REPRESENTATIVE

6. MASONRY CONSTRUCTION CONT.				
LEVEL 2 INSPECTION:	ENGINEERED MASONRY IN ESSENTIAL FACILITIES.	IBC 1704.5.3		QUALIFICATIONS BASED ON C1093
A. FROM THE BEGINNING OF MASONRY CONSTRUCTION, THE FOLLOWING SHALL BE VERIFIED TO ENSURE COMPLIANCE:	<ul style="list-style-type: none"> 1. PROPORTIONS OF SITE-PREPARED MORTAR, GROUT, AND PRESTRESSING GROUT FOR BONDED TENDONS. 2. PLACEMENT OF MASONRY UNITS AND CONSTRUCTION OF MORTAR JOINTS. 3. PLACEMENT OF REINFORCEMENT, CONNECTORS, AND PRESTRESSING TENDONS AND ANCHORAGES. 4. GROUT SPACE PRIOR TO GROUTING. 5. PLACEMENT OF GROUT. 6. PLACEMENT OF PRESTRESSING GROUT. 			
B. THE INSPECTION PROGRAM SHALL VERIFY:	<ul style="list-style-type: none"> 1. SIZE AND LOCATION OF STRUCTURAL ELEMENTS. 2. TYPE, SIZE AND LOCATION OF ANCHORS, INCLUDING OTHER DETAILS OF ANCHORAGE OF MASONRY TO STRUCTURAL MEMBERS, FRAMES, OR OTHER CONSTRUCTION. 3. SPECIFIED SIZE, GRADE AND TYPE OF REINFORCEMENT. 4. WELDING OF REINFORCEMENT. 5. PROTECTION OF MASONRY DURING COLD WEATHER (TEMPERATURE BELOW 40 DEGREES F) OR HOT WEATHER (TEMPERATURE ABOVE 90 DEGREES F). 6. APPLICATION AND MEASUREMENT OF PRESTRESSING FORCE. 			
C. PREPARATION OF ANY REQUIRED GROUT SPECIMENS, MORTAR SPECIMENS AND/OR PRISMS SHALL BE OBSERVED.	<ul style="list-style-type: none"> 1. VERIFY COMPLIANCE WITH CODE AND CONSTRUCTION DOCUMENTS PROVISIONS. 			QUALIFICATIONS BASED ON C1093
D. COMPLIANCE WITH REQUIRED INSPECTION PROVISIONS OF THE CONSTRUCTION DOCUMENTS AND THE APPROVED SUBMITTALS SHALL BE VERIFIED.	<ul style="list-style-type: none"> 1. VERIFY COMPLIANCE WITH CODE AND CONSTRUCTION DOCUMENTS PROVISIONS. 			QUALIFICATIONS BASED ON C1093
E. TESTING OF GROUT SPECIMENS, MORTAR SPECIMENS AND/OR PRISMS.	<ul style="list-style-type: none"> 1. TEST ONE SET OF MORTAR CUBES PER 2000 sq OR PORTION THEREOF. 2. TEST ONE SET OF GROUT CYLINDERS PER 2000 sq OR PORTION THEREOF. 3. TEST ONE PRISM PER 6000 sq OR PORTION THEREOF. (SUBMITTED PRISM WILL BE ACCEPTABLE FOR FIRST PRISM TEST). 			QUALIFICATIONS BASED ON C1093

3. CONCRETE CONSTRUCTION CONT.				
G. PLACEMENT OF CONCRETE & SHOTCRETE.	CONTINUOUS		ACI 318-CH. 5.9, 5.10	QUALIFICATIONS BASED ON ASTM C1077
H. MAINTENANCE OF SPECIFIED CURING TEMPERATURE & TECHNIQUES.	PERIODIC	EACH CONCRETE POUR	ACI 318-CH. 5.11, 5.13	QUALIFICATIONS BASED ON ASTM C1077
I. PRESTRESSED CONCRETE.	NA	1. APPLICATION OF PRESTRESSING FORCE 2. GROUTING OF BONDED PRESTRESSING TENDONS IN SEISMIC-FORCE RESISTING SYSTEMS.		QUALIFICATIONS BASED ON ASTM C1077
J. ERECTION OF PRECAST CONCRETE MEMBERS.	NA			TECHNICIAN TRAINED IN FIELD OF WORK AND HAS AT LEAST ONE YEAR OF EXPERIENCE.
K. POST-TENSIONED CONCRETE.	NA	1. VERIFY IN-SITU CONCRETE STRENGTH PRIOR TO STRESSING OF TENDONS.		QUALIFICATIONS BASED ON ASTM E829
	NA	2. THE POST-TENSIONING ENGINEER OR A MEMBER OF HIS STAFF SHALL INSPECT THE TENDON PLACEMENT AND CHAIRING TO INSURE COMPLIANCE WITH THE INTENT OF THE DESIGN.		
	NA	3. CONTINUOUS INSPECTION IS REQUIRED DURING ALL STRESSING ACTIVITIES.		
	NA	4. RECORDS OF ALL JACKING FORCES AND ELONGATIONS SHALL BE MADE IN ACCORDANCE WITH THE PTF FIELD MANUAL AND RECORDS SHALL BE PROMPTLY SUBMITTED TO THE ARCHITECT AND ENGINEER.		
L. REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS.	PERIODIC	VERIFY IN-SITU CONCRETE STRENGTH PRIOR TO REMOVAL.	ACI 318-CH. 5.11, 5.13	QUALIFICATIONS BASED ON ASTM E829
M. POST INSTALLED REINFORCING & ANCHORS (EXPANSION ANCHORS, SCREW ANCHORS ADHESIVE ANCHORS, ECT.).	CONTINUOUS	THE SPECIAL INSPECTOR SHALL BE ON THE JOB SITE CONTINUOUSLY DURING ANCHOR INSTALLATION TO VERIFY ANCHOR TYPE, ANCHOR DIMENSIONS, CONCRETE TYPE AND COMPRESSION STRENGTH. PRE-DRILLED HOLE DIMENSIONS ANCHOR SPACING, EDGE DISTANCES, CONCRETE THICKNESS AND ANCHOR EMBEDMENT.	ACI 318 APPENDIX D-CH. D.9.1	QUALIFICATIONS BASED ON ASTM E829 & ASTM C1077 OR CERTIFIED MANUFACTURER REPRESENTATIVE

4. STEEL CONSTRUCTION				
A. MATERIAL VERIFICATION OF HIGH-STRENGTH BOLTS, NUTS AND WASHERS.	NA	1. IDENTIFICATION MARKINGS TO CONFORM TO ASTM STANDARDS SPECIFIED IN THE APPROVED CONSTRUCTION DOCUMENTS.	STRUCTURAL STEEL GENERAL NOTES	CW/ASSOCIATE/TECHNICAL RADIATE, AWS OR CRSI
	NA	2. MANUFACTURER'S CERTIFICATE OF COMPLIANCE REQUIRED.	APPLICABLE ASTM MATERIAL SPECIFICATIONS: AISC 336, SECTION A3.4; AISC LRFD, SECTION A3.3	
4. STEEL CONSTRUCTION CONT.:			IBC 1704.3	
B. HIGH STRENGTH BOLTING:	NA	1. BEARING-TYPE CONNECTIONS.	IBC 1705.2 STRUCTURAL STEEL GENERAL NOTES	CW/ASSOCIATE/TECHNICAL RADIATE, AWS OR CRSI
	NA	2. SLIP-CRITICAL CONNECTIONS.	AWSD, SECTION A3.6; AISC LRFD, SECTION A3.5	
C. MATERIAL VERIFICATION OF STRUCTURAL STEEL.	NA	1. IDENTIFICATION MARKINGS TO CONFORM TO ASTM STANDARDS SPECIFIED IN THE APPROVED CONSTRUCTION DOCUMENTS.	IBC 1705.2 STRUCTURAL STEEL GENERAL NOTES	CW/ASSOCIATE/TECHNICAL RADIATE, AWS OR CRSI
	NA	2. MANUFACTURER'S CERTIFIED MILL TEST REPORTS.	ASTM A 6 OR ASTM A 588	
D. MATERIAL VERIFICATION OF WELD FILLER MATERIALS:	NA	1. IDENTIFICATION MARKINGS TO CONFORM TO AWS SPECIFICATION IN THE APPROVED CONSTRUCTION DOCUMENTS.	STRUCTURAL STEEL GENERAL NOTES	CW/ASSOCIATE/TECHNICAL RADIATE, AWS OR CRSI
	NA	2. MANUFACTURER'S CERTIFIED OF COMPLIANCE REQUIRED.	AWSD, SECTION A3.6; AISC LRFD, SECTION A3.5	
E. WELDING OF STRUCTURAL STEEL:	NA	1. COMPLETE & PARTIAL PENETRATION GROOVE WELDS.	IBC 1705.2.1 STRUCTURAL STEEL GENERAL NOTES	CW AND ASNT
	NA	2. MULTIPASS FILLET WELDS.	AWSD D.1	CW AND ASNT OR LICENSED ENGINEER
	NA	3. SINGLE-PASS FILLET WELDS > 5/16"		
	NA	4. SINGLE-PASS FILLET WELDS < 5/16"		
	NA	5. FLOOR AND DECK WELDS.	AWSD D.13	
F. WELDING OF REINFORCING STEEL:	NA	1. VERIFICATION OF WELD ABILITY OF REINFORCING STEEL OTHER THAN A305.	IBC 1705.2.2.1 STEEL	CW/ASSOCIATE/TECHNICAL TRAINED IN FIELD OF WORK AND HAS AT LEAST ONE YEAR OF EXPERIENCE.
	NA	2. REINFORCING STEEL RESISTING FLEXURAL AND AXIAL FORCES IN INTERMEDIATE AND SPECIAL MOMENT FRAMES, AND BOUNDARY ELEMENTS OF SPECIAL REINFORCED CONCRETE SHEAR WALLS AND SHEAR REINFORCEMENT.		
	NA	3. SHEAR REINFORCEMENT.		
	NA	4. OTHER REINFORCING STEEL.		
G. STEEL FRAME JOINT DETAILS: COMPLIANCE WITH APPROVED CONSTRUCTION DOCUMENTS:	NA	1. DETAILS SUCH AS BRACING & STIFFENING.	IBC 1705.2.1 STRUCTURAL DRAWINGS	PROJECT OF COMPLEX DETAILS - ASSOCIATE CWI PROJECTS OF RELATIVELY SIMPLE DETAILS. TECHNICIAN TRAINED IN FIELD OF WORK AND HAS AT LEAST ONE YEAR OF EXPERIENCE.
	NA	2. MEMBER LOCATIONS.		
	NA	3. APPLICATION OF JOINT DETAILS AT EACH CONNECTION.		
H. POST INSTALLED REINFORCING & ANCHORS (EXPANSION ANCHORS, SCREW ANCHORS ADHESIVE ANCHORS, ECT.).	NA	THE SPECIAL INSPECTOR SHALL BE ON THE JOB SITE CONTINUOUSLY DURING ANCHOR INSTALLATION TO VERIFY ANCHOR TYPE, ANCHOR DIMENSIONS, CONCRETE OR MASONRY TYPE AND COMPRESSION STRENGTH. PRE-DRILLED HOLE DIMENSIONS, ANCHOR SPACING, EDGE DISTANCES, CONCRETE OR MASONRY THICKNESS AND ANCHOR EMBEDMENT.	ACI 318 APPENDIX D-CH. D.9.1	QUALIFICATIONS BASED ON ASTM E829 & ASTM C1077 OR CERTIFIED MANUFACTURER REPRESENTATIVE

5. INSPECTION OF FABRICATORS FOR STRUCTURAL STEEL				
FABRICATION & IMPLEMENTATION PROCEDURES	NA	FABRICATION AND IMPLEMENTATION PROCEDURES. THE SPECIAL INSPECTOR SHALL VERIFY THAT THE FABRICATOR MAINTAINS DETAILED FABRICATION AND QUALITY CONTROL RECORDS OF THE WORKMANSHIP AND THE FABRICATOR'S ABILITY TO CONFORM TO APPROVED CONSTRUCTION DOCUMENTS AND REFERENCED STANDARDS. THE SPECIAL INSPECTOR SHALL REVIEW THE PROCEDURES FOR COMPLETENESS AND ADEQUACY RELATIVE TO THE CODE REQUIREMENTS FOR THE FABRICATOR'S SCOPE OF WORK. EXCEPTION: SPECIAL INSPECTIONS SHALL NOT BE REQUIRED WHERE THE WORK IS DONE ON THE PREMISES OF A FABRICATOR THAT IS ENROLLED IN A NATIONALLY ACCEPTED INSPECTIONS PROGRAM ACCEPTABLE TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE. AT COMPLETION OF FABRICATION, THE APPROVED FABRICATOR SHALL SUBMIT A CERTIFICATE OF COMPLIANCE TO BUILDING OFFICIAL. UPON REQUEST AND TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE STATING THAT THE WORK WAS PERFORMED IN ACCORDANCE WITH THE APPROVED CONSTRUCTION DOCUMENTS.	IBC 1705.2.1	CW/ ASNT, LICENSED ENGINEER
A. REINFORCING STEEL	PERIODIC	PROVIDE PERIODIC INSPECTION OF REINFORCING SIZES, SPACING, GRADE OF REBAR, AND PLACEMENT AT THE FOLLOWING FREQUENCY: COILS: 10% BEAMS: 30% JOIST: 10% OTHER MEMBERS: RANDOMLY @ 20%	IBC 1705.3	QUALIFICATIONS BASED ON ASTM E829
B. REINFORCING STEEL WELDING	-	NO FIELD WELDING PERMITTED.	AWSD D.1 & ACI 318 3.5.2	CW/ OR ASSOCIATE CWI
C. BOLTS TO BE INSTALLED IN CONCRETE PRIOR TO & DURING PLACEMENT OF CONCRETE WHERE ALLOWABLE LOADS HAVE BEEN INCREASED.	CONTINUOUS	VERIFY LOCATION, SIZE AND SPACING OF ANCHORS.	IBC 1705.3	"TECHNICIAN TRAINED IN FIELD OF WORK AND HAS AT LEAST ONE YEAR EXPERIENCE."
D. ANCHORS TO BE INSTALLED IN EXISTING CONCRETE	CONTINUOUS	VERIFY LOCATION, SIZE AND SPACING OF ANCHORS	IBC 1705.3	"TECHNICIAN TRAINED IN FIELD OF WORK AND HAS AT LEAST ONE YEAR EXPERIENCE."
E. VERIFY USE OF CONCRETE MIX DESIGN	PERIODIC	EACH CONCRETE POUR	ACI 318-CH. 4, 5.2.4	QUALIFICATIONS BASED ON ASTM C1077
F. SAMPLES OF FRESH CONCRETE.	CONTINUOUS EACH CONCRETE POUR	1. ALL CONCRETE TESTING IS TO BE MADE AFTER WATER, IF ANY, IS ADDED AT SITE. 2. TAKE SAMPLES & PERFORM SLUMP, AIR & COMPRESSION TESTS IN ACCORDANCE WITH ASTM C-39 ON CONCRETE PLACED EACH DAY AT THE RATE OF ONE SET OF FOUR CYLINDERS FOR EACH 80 cu. yds. OR FRACTION THEREOF. WHEN MORE THAN 80 cu. yds. IS BEING CONTINUOUSLY PLACED, THE INTERVAL BETWEEN TEST SAMPLES SHALL BE AT LEAST 90 cu. yds. SO AS TO BE REPRESENTATIVE OF THE WHOLE DAYS POUR. SAMPLES SHALL BE TAKEN AT THE POINT OF DEPOSIT IN THE FIELD & ALL CYLINDERS SHALL BE ACCURATELY MARKED & REFERENCED TO SHOW DATE, TIME & EXACT LOCATION IN THE STRUCTURE FROM WHICH THEY CAME. MAKE 7-DAY TEST ON TWO CYLINDERS & 28-DAY TEST ON TWO CYLINDERS. REPORTS OF TESTS SHALL BE PROMPTLY SENT AS FOLLOWS: TWO TO THE PORTING (ARCHITECT), ONE TO THE ENGINEER AND ONE TO THE CONTRACTOR.	ACI 318-CH. 5.6, 5.8	QUALIFICATIONS BASED ON ASTM C1077

Pursuant to IBC Chapter 17 (1704.2.1) provide the following Special Inspector Qualifications to the RDP/RC prior to start of inspections;

- Testing Laboratory Qualifications meeting ASTM0329 and accreditation by AASHTO and/or A2LA, and CCRL of the National Bureau of Standards.
- Special Inspector's name and proof of meeting the qualification requirements set forth in:
 - ASTM C1077 for concrete,
 - ASTM D3740 for soils,
 - ASTM C1093 for masonry.
 - ASTM D-2922 and D-3017 for Density control of compaction

IBC 1704.2.1 "written documentation demonstrating the competence and relevant experience or training of special inspectors who will perform special inspections and tests during construction. Experience or training shall be considered relevant where the documented experience or training is related in complexity to the same type of special inspection or testing activities for projects of similar complexity and material qualities." These qualifications are in addition to qualifications specified in other sections of the IBC.

TESTING & INSPECTION REQUIREMENTS (INCLUDING SPECIAL INSPECTIONS)

REQUIRED INSPECTION VERIFICATION, OR TEST	VERIFICATION MONITORING FREQUENCY	TYPE AND/OR FREQUENCY OF TESTING	IBC SECTION & REFERENCE CODES	INSPECTOR QUALIFICATIONS
1. SOILS (SLAB ON GRADE)				
A. SUB-GRADE	PERIODIC	SITE PREPARATION: AT THE CONTRACTOR'S EXPENSE, INSTRUMENT READINGS SHALL BE TAKEN BY A LICENSED SURVEYOR TO VERIFY FINAL SUBGRADE ELEVATIONS AND SLOPES.	IBC 1705.6	QUALIFICATIONS BASED ON ASTM D3740 LICENSED SURVEYOR
2. PROFFROLLING OBSERVATIONS	CONTINUOUS	PROFFROLLING SHALL BE MONITORED BY A GEOTECHNICAL ENGINEER SHALL BE APPROVE THE TYPE OF PROFFROLLING EQUIPMENT AND PROCEDURES. PROVIDE (1) ON DENSITY TEST FOR EACH 3000 SQ. FT. REFER TO UNDERFLOOR FILL NOTES FOR TESTING SPECIFICATIONS.	IBC 1705.6	QUALIFICATIONS BASED ON ASTM D3740
3. MOISTURE CONDITIONING & CURE	PERIODIC	PROVIDE (1) ON DENSITY TEST FOR EACH 3000 SQ. FT. REFER TO UNDERFLOOR FILL NOTES FOR TESTING SPECIFICATIONS.	IBC 1705.6	QUALIFICATIONS BASED ON ASTM D3740
B. CHEMICAL INJECTION	NA	QUALITY CONTROLLED TESTING AND EVALUATION PRIOR AND SUBSEQUENT TO INJECTION SHALL BE PERFORMED BY THE GEOTECHNICAL ENGINEER TO DETERMINE THE EFFECTIVENESS OF THE CHEMICAL INJECTION PROCESS. THE GEOTECHNICAL ENGINEER OR HIS REPRESENTATIVE SHALL MONITOR THE INJECTION PROCESS TO VERIFY AREA COVERAGE, INJECTION DEPTH AND TO REVIEW AND MONITOR THE SWELL TEST RESULTS.	IBC 1705.6	QUALIFICATIONS BASED ON ASTM D3740
C. DURING FILL PLACEMENT	PERIODIC	VISUAL OBSERVATIONS: DURING PLACEMENT AND COMPACTON OF FILL, SPECIAL INSPECTOR SHALL DETERMINE THE MATERIAL BEING USED AND THE MAXIMAL LIFT THICKNESS COMPLY WITH ADDITIONAL SAMPLES TESTED EACH DAY, OR MORE OFTEN IF MATERIAL APPEARS TO VARY.	IBC 1705.6	QUALIFICATIONS BASED ON ASTM D3740
D. EVALUATION OF IN-PLACE DENSITY OF FILL	PERIODIC	PROVIDE (1) ON DENSITY TEST FOR EACH 3000 SQ. FT. REFER TO UNDERFLOOR FILL NOTES FOR TESTING SPECIFICATIONS.	IBC 1705.6	QUALIFICATIONS BASED ON ASTM D3740
E. TRENCH BACKFILLING:	PERIODIC	TRENCH BACKFILLING: TRENCH BACKFILLING WITH CLAY CAP AND PLACING OF CLAY PLUG SHALL BE MONITORED BY GEOTECHNICAL ENGINEER.		
2A. PILE FOUNDATIONS				
A. THE GEOTECHNICAL ENGINEER OR A QUALIFIED E.I.T. INVOLVED IN THE ORIGINAL GEOTECHNICAL INVESTIGATION AND UNDER THE DIRECT SUPERVISION OF THE GEOTECHNICAL ENGINEER SHALL BE PRESENT DURING THE EXCAVATION OF THE FIRST PILE.	NA	1. VERIFY THE BEARING STRATH IS ENCOUNTERED AT THE ANTICIPATED DEPTH. 2. ADDRESS UNFORESEEN SUBSURFACE CONDITIONS, IF ANY. 3. VERIFY CONFORMANCE WITH THE FOUNDATION RECOMMENDATIONS PROVIDED IN THE PROJECT "GEOTECHNICAL ENGINEERING STUDY" AND THE STRUCTURAL DRAWINGS ISSUED FOR THE PROJECT.	IBC 1705.7	GRADUATE ENGINEER GEOTECHNICAL REPORT: QUALIFICATIONS BASED ON ASTM E829 & ASTM C1077
B. ALL FOOTINGS SHALL BE OBSERVED AND MONITORED BY A REPRESENTATIVE OF THE GEOTECHNICAL ENGINEER. THE CONTRACTOR SHALL PROVIDE A COMPLETE SET OF STRUCTURAL DRAWINGS THAT ARE TO REMAIN WITH THE GEOTECHNICAL ENGINEER OR HIS REPRESENTATIVE.	NA	1. PROVIDE RECORD OF EACH PILE INSTALLED. 2. RECORD LOAD TESTS, CUTOFF AND TIP OF EACH PILE.	IBC 1705.7	QUALIFICATIONS BASED ON ASTM E829 & ASTM C1077
A. THE GEOTECHNICAL ENGINEER OR A QUALIFIED E.I.T. INVOLVED IN THE ORIGINAL GEOTECHNICAL INVESTIGATION AND UNDER THE DIRECT SUPERVISION OF THE GEOTECHNICAL ENGINEER SHALL BE PRESENT DURING THE EXCAVATION OF THE FIRST PIER SHAFT.	CONTINUOUS	1. VERIFY THE BEARING STRATH IS ENCOUNTERED AT THE ANTICIPATED DEPTH. 2. ADDRESS UNFORESEEN SUBSURFACE CONDITIONS, IF ANY. 3. VERIFY CONFORMANCE WITH THE FOUNDATION RECOMMENDATIONS PROVIDED IN THE PROJECT "GEOTECHNICAL ENGINEERING STUDY" AND THE STRUCTURAL DRAWINGS ISSUED FOR THE PROJECT.	IBC 1705.8	GRADUATE ENGINEER GEOTECHNICAL REPORT: QUALIFICATIONS BASED ON ASTM E829 & ASTM C1077
B. ALL FOOTINGS SHALL BE OBSERVED AND MONITORED BY A REPRESENTATIVE OF THE GEOTECHNICAL ENGINEER WITH A COMPLETE SET OF STRUCTURAL DRAWINGS THAT ARE TO REMAIN WITH THE GEOTECHNICAL ENGINEER OR HIS REPRESENTATIVE.	CONTINUOUS	1. PROVIDE RECORD OF EACH PIER INSTALLED. 2. RECORD LOAD TESTS, CUTOFF AND TIP OF EACH PIER.	IBC 1705.8	QUALIFICATIONS BASED ON ASTM E829 & ASTM C1077
3. CONCRETE CONSTRUCTION				
A. REINFORCING STEEL	PERIODIC	PROVIDE PERIODIC INSPECTION OF REINFORCING SIZES, SPACING, GRADE OF REBAR, AND PLACEMENT AT THE FOLLOWING FREQUENCY: COILS: 10% BEAMS: 30% JOIST: 10% OTHER MEMBERS: RANDOMLY @ 20%	IBC 1705.3	QUALIFICATIONS BASED ON ASTM E829
B. REINFORCING STEEL WELDING	-	NO FIELD WELDING PERMITTED.	AWSD D.1 & ACI 318 3.5.2	CW/ OR ASSOCIATE CWI
C. BOLTS TO BE INSTALLED IN CONCRETE PRIOR TO & DURING PLACEMENT OF CONCRETE WHERE ALLOWABLE LOADS HAVE BEEN INCREASED.	CONTINUOUS	VERIFY LOCATION, SIZE AND SPACING OF ANCHORS.	IBC 1705.3	"TECHNICIAN TRAINED IN FIELD OF WORK AND HAS AT LEAST ONE YEAR EXPERIENCE."
D. ANCHORS TO BE INSTALLED IN EXISTING CONCRETE	CONTINUOUS	VERIFY LOCATION, SIZE AND SPACING OF ANCHORS	IBC 1705.3	"TECHNICIAN TRAINED IN FIELD OF WORK AND HAS AT LEAST ONE YEAR EXPERIENCE."
E. VERIFY USE OF CONCRETE MIX DESIGN	PERIODIC	EACH CONCRETE POUR	ACI 318-CH. 4, 5.2.4	QUALIFICATIONS BASED ON ASTM C1077
F. SAMPLES OF FRESH CONCRETE.	CONTINUOUS EACH CONCRETE POUR	1. ALL CONCRETE TESTING IS TO BE MADE AFTER WATER, IF ANY, IS ADDED AT SITE. 2. TAKE SAMPLES & PERFORM SLUMP, AIR & COMPRESSION TESTS IN ACCORDANCE WITH ASTM C-39 ON CONCRETE PLACED EACH DAY AT THE RATE OF ONE SET OF FOUR CYLINDERS FOR EACH 80 cu. yds. OR FRACTION THEREOF. WHEN MORE THAN 80 cu. yds. IS BEING CONTINUOUSLY PLACED, THE INTERVAL BETWEEN TEST SAMPLES SHALL BE AT LEAST 90 cu. yds. SO AS TO BE REPRESENTATIVE OF THE WHOLE DAYS POUR. SAMPLES SHALL BE TAKEN AT THE POINT OF DEPOSIT IN THE FIELD & ALL CYLINDERS SHALL BE ACCURATELY MARKED & REFERENCED TO SHOW DATE, TIME & EXACT LOCATION IN THE STRUCTURE FROM WHICH THEY CAME. MAKE 7-DAY TEST ON TWO CYLINDERS & 28-DAY TEST ON TWO CYLINDERS. REPORTS OF TESTS SHALL BE PROMPTLY SENT AS FOLLOWS: TWO TO THE PORTING (ARCHITECT), ONE TO THE ENGINEER AND ONE TO THE CONTRACTOR.	ACI 318-CH. 5.6, 5.8	QUALIFICATIONS BASED ON ASTM C1077




ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608




ENGINEERING
580 HEINER ROAD PH 018 979-7900
SAN ANTONIO, TEXAS 78232 FX 018 979-7800
TX FIRM REG. #3388

1801 Marlin Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION







CLIENT		
Alamo Colleges	PROJECT NUMBER	230462
DATE	2024/05/23	
DRAWING HISTORY		
No.	Description	Date
2	City Comments	06/12/24

ISSUE FOR CONSTRUCTION
BUILDING NUMBER **AB**
SPECIAL INSPECTION NOTES



MECHANICAL YARD FOUNDATION PLAN
SCALE: 1/4" = 1'-0"



SIZE	CLEAR OPENING		REMARKS
	GREATER THAN	UP TO	
ONE COURSE	-	4'-0"	8" BEARING @ EA. END
TWO COURSE	4'-0"	6'-6"	8" BEARING @ EA. END
THREE COURSE	6'-6"	14'-0"	8" BEARING @ EA. END

MASONRY WALL REINFORCEMENT:

MN-1 PROVIDE GROUDED REINFORCED VERTICAL CELLS AND HORIZONTAL BOND BEAMS AT WALL TOP EDGES, CORNERS, FREE ENDS, WINDOW AND DOOR JAMBS, LINTELS AND OTHER LOCATIONS WHERE SHOWN ON ARCHITECTURAL DRAWINGS. REINFORCE EACH GROUDED CELL AND BOND BEAM WITH 1-#4 BAR CONTINUOUS (REINFORCE LINTELS AS SPECIFIED BELOW).

MN-2 BASIC VERTICAL REINFORCEMENT FOR EXTERIOR WALLS SHALL BE #4 @ 32" o.c. (EVERY 4th VERTICAL CELL).




MN-3 PROVIDE GROUDED REINFORCED LINTELS WITH 8" BEARING EACH END OF ALL DOORS, WINDOWS, AND OTHER OPENINGS. USE ONE-COURSE LINTELS FOR OPENINGS UP TO 4'-0"; TWO-COURSE LINTELS FOR OPENINGS UP TO 6'-6"; THREE-COURSE LINTELS FOR OPENINGS UP TO 14'-0". REINFORCE EACH COURSE WITH 2-#5 BAR CONTINUOUS.

MN-4 PROVIDE MATCHING DOWELS IN FOUNDATION FOR ALL VERTICAL REINFORCEMENT.

MN-5 CMU SHALL HAVE A UNIT STRENGTH OF 1,900 PSI. USE TYPE S MORTAR. REINFORCED CMU SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 7,000 PSI. GROUT FOR FILLED CELLS SHALL BE MADE OF CEMENT, SAND AND PEA GRAVEL IN APPROXIMATE RATIO OF 1:3:2 AND SHALL HAVE 28-DAY COMPRESSIVE STRENGTH OF 2,500 PSI.

MN-6 ANCHOR MASONRY TO STRUCTURE AS SHOWN IN DETAILS. SEE SPECIFICATIONS FOR ORDINARY MASONRY ANCHORS INCLUDING DOVETAIL ANCHOR SLOTS IN ADJACENT CONCRETE MEMBERS.

MN-7 LEVEL 1 INSPECTED MASONRY REQUIRES CONTRACTOR TO SUBMIT, AT CONTRACTOR'S COST, COMPRESSIVE WALL DESIGN STRENGTH (Fm) VERIFIED BY INDEPENDENT TESTING LAB BY PRISM TESTS BEFORE MASONRY CONSTRUCTION BEGINS. PROVIDE UNIT MASONRY STRENGTH, GROUT MIX DESIGN AND MORTAR MIX DESIGN.



MARK	W x D*	GRADE BEAM SCHEDULE	
		MAIN REINFORCING	TIES
GB1	12 x 24"	2-#6 x CONT. TOP & BOTTOM	#3 @ 24" o.c.
GB2	18 x 24"	3-#6 x CONT. TOP & BOTTOM	#3 @ 24" o.c.

* REF. NOTE FN-4

FOUNDATION NOTES:

FN-1 5" CONCRETE SLAB REINFORCED W/ #4 @ 12" o.c. EACH WAY IN TOP. SUPPORT AT 4'-0" o.c. EACH WAY WITH CONCRETE BLOCKS OR BRICKS. SUPPORT BOTTOM BEAM REINFORCEMENT AT 4'-0" INTERVALS.

FN-2 15 MIL. POLYOLEFIN VAPOR RETARDER UNLESS NOTES OTHERWISE IN SPECIFICATIONS. AT ALL JOINTS PROVIDE 6" LAPS W/ 4" TAPE.

FN-3 COMPACTED SELECT FILL (SEE UF-6 "UNDERFLOOR FILL NOTES").

FN-4 ALL BEAM SOFFITS SHALL BEAR 24" MINIMUM INTO NATURAL GRADE OR COMPACTED FILL. ON PERIMETER, INCREASE SCHEDULED BEAM DEPTH AS REQUIRED FOR SOFFIT TO BEAR 24" MINIMUM BELOW FINISH GRADE. REF GEOTECHNICAL REPORT. ALL PERIMETER GRADE BEAMS SHALL BEAR ON LIMESTONE.

FN-5 GRADE BEAMS AND SLAB TURNDOWNS SHALL BE FORMED BY WALLS AND SOFFIT OF CAREFULLY SHAPED TRENCH. USE A SMOOTH-MOUTHED BUCKET. IF A TOOTHED BUCKET IS USED, EXCAVATION SHALL BE STOPPED 6" ABOVE FINAL GRADE AND THE REMAINING EXCAVATION ACCOMPLISHED WITH A SMOOTH MOUTHED BUCKET OR BY HAND LABOR TO REMOVE ALL LOOSE SOILS DISTURBED BY THE BUCKET TEETH. WOODFORM EXPOSED FACES TO A DEPTH OF 8" BELOW FINISHED GRADE.

FN-6 AT ALL BEAM CORNERS & T-INTERSECTIONS, PROVIDE 4-#7 x 6'-0" CORNER BARS (2-TOP AND 2-BOTTOM).

FN-7 TRENCHES SHALL BE VERIFIED FOR SIZE TO MAINTAIN CLEARANCES AROUND REINFORCEMENT PRIOR TO PLACING REINFORCEMENT.

FN-8 WHERE BEAM DEPTH EXCEEDS 36", ADD #4 @ 12" o.c. IN EACH FACE OF BEAM.

UNDERFLOOR FILL NOTES:

UF-1 BEFORE ANY CONSTRUCTION IS BEGUN, PERFORM ROUGH GRADING AND CUT SWALES SO THAT GROUNDS WILL DRAIN AWAY FROM THE BUILDING. MAINTAIN DRAINAGE DURING ALL PHASES OF CONSTRUCTION SO THAT STORM WATER WILL BE CONDUCTED AWAY FROM THE BUILDING. KEEP EXCAVATIONS PUMPED FREE OF STORM WATER AT ALL TIMES.

UF-2 PRECAUTIONS SHALL BE TAKEN TO PROTECT OPEN EXCAVATIONS FROM EXCESSIVE LOSS OR GAIN IN NATURAL MOISTURE LEVEL PRIOR TO PLACEMENT OF BASE MATERIAL. KEEP MOIST DURING DRY WEATHER AND KEEP STORM WATER PUMPED OUT, INCLUDING NIGHTS AND WEEKENDS, DURING RAINS.

UF-3 IN THE AREA OCCUPIED BY THE FOUNDATION AND ALL ADJACENT SIDEWALKS, PLUS 3'-0", REMOVE A MINIMUM OF 7'-0" OF TOPSOIL INCLUDING ALL ORGANIC MATERIALS, ROOTS, ETC. FROM THE SITE. DO NOT USE FOR UNDERFLOOR FILL. REMOVE ADDITIONAL MATERIAL AS NECESSARY TO PROVIDE A MINIMUM OF 7'-0" OF SELECT FILL AS PER UF-6.

UF-4 THE RESULTING SURFACE SHALL BE PROOF ROLLED WITH A SUFFICIENTLY HEAVY ROLLER (15 TONS) TO LOCATE AND DENSITY WEAK AND COMPRESSIBLE ZONES. A MINIMUM OF 6 PHASSES OF THE ROLLER IS REQUIRED. ANY SOFT SPOTS SHALL BE REMOVED AND REPLACED WITH COMPACTED SELECT FILL.

UF-5 THE ROLLED SUBGRADE SHALL BE SCARIFIED JUST PRIOR TO FILL PLACEMENT TO A MINIMUM DEPTH OF 6" AND RECOMPACTED TO MINIMUM OF 95% OF THE MAXIMUM DENSITY DETERMINED BY ASTM D698 COMPACTION TEST, MAINTAINING MOISTURE CONTENT BETWEEN -1 AND +3 PERCENTAGE POINTS UNTIL COVERED.

UF-6 FOR A DISTANCE OF 3'-0" OUTSIDE OF THE BUILDING LINE AND ALL ADJACENT SIDEWALKS, AND BEGINNING AT THE LOW END, BUILD UP TO THE ELEVATION OF THE BOTTOM OF THE SLAB WITH SELECT CRUSHED STONE FILL CONFORMING TO TxDOT SPECIFICATIONS, ITEM 247, TYPE "A" GRADE 2. A MINIMUM THICKNESS OF 7'-0" IS REQUIRED. NO DIRT FILL SHALL BE USED UNDER THE BUILDING FOUNDATION. SUBMIT WRITTEN CERTIFICATION OF COMPLIANCE WITH TxDOT, ITEM 247 SPECIFICATIONS BY TEST PERFORMED ON FIELD EXAMPLES.

UF-7 ALL FILL SHALL BE PLACED IN 8" LOOSE HORIZONTAL LIFTS AND COMPACTED TO A MINIMUM OF 95% OF THE MAXIMUM DENSITY AS DETERMINED BY ASTM D698 COMPACTION TEST. MAINTAINING MOISTURE CONTENT BETWEEN -1 AND +3 PERCENTAGE POINTS UNTIL COVERED. EXCESS FILL AT BUILDING PERIMETER SHALL BE CUT AND GRADED TO COMPLY WITH FINISHED GRADE REQUIREMENTS, AND SHALL BE OVERLAIN WITH A 1'-0" THICK LAYER OF IMPERVIOUS CLAY FOR A MINIMUM DISTANCE OF 5'-0" FROM BUILDING LINE. REFER TO DETAIL 777.


UF-8 PERFORM ALL EARTH WORK DESCRIBED ABOVE BEFORE TRENCHING FOR GRADE BEAMS OR MECHANICAL LINES.

UF-9 REFERENCE GEOTECHNICAL REPORT BY: ? PROJECT No. ?, DATED ?.



ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-823-5578 F
TX Firm BR 1608

ENGINEERING
LUNDY & FRANK
588 HEIMER ROAD PH 018 979-7900
SAN ANTONIO, TEXAS 78232 FX 010 979-7800
TX FIRM REG. #388



CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date


ISSUE FOR CONSTRUCTION
BUILDING NUMBER AB

SECTIONS, DETAILS & MECH. YARD FOUNDATION

S-301

ISSUE FOR CONSTRUCTION

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-Blackbox Addition Structural R23



1 SECTION
1/2" = 1'-0"

EE

W




ARCHITECT	PBK Architects, Inc. 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-5578 F TX Firm BR 1606
ASSOCIATE ARCHITECT	BA ARCHITECTS 1111 N. Loop West San Antonio, TX 78205
CONSULTANT	LANDSCAPE ROSE AND DESIGN 1111 N. Loop West San Antonio, TX 78205
STRUCTURAL	LUNDY & FRANKE ENGINEERING 548 HEIMER ROAD SAN ANTONIO, TEXAS 78232 PH: 210-529-5172 FX: 210-529-5173 TX FIRM REG. #3388
MECHANICAL	
ELECTRICAL	
PLUMBING	
BEAM PROFESSIONALS	
MEASUREMENT	
TESTING	

LUNDY & FRANKE ENGINEERING
548 HEIMER ROAD
SAN ANTONIO, TEXAS 78232
TX FIRM REG. #3388
PH: 210-529-5172
FX: 210-529-5173

WFAC Black Box Addition PKG 1

1801 Main, Luther King Dr.,
San Antonio, TX, 78203
ISSUE FOR CONSTRUCTION



DATE: 06/12/2024


SHAWN J. FRANKE
82639
LICENSED PROFESSIONAL ENGINEER
Shawn Franke

CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
2024/05/23		
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER		AB

SECTION

S-302

ISSUE FOR CONSTRUCTION



1 SECTION
3/8" = 1'-0"

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-38blackbox Addition, Structural R23




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-5578 F TX Firm BR 1606	
ASSOCIATE ARCHITECT	BA & ARCHITECTS
DATE	05/23/24
DESIGNER	TRAVIS HALL
LANDSCAPE	LANDSCAPE
ROSE AND DESIGN	TRAVIS HALL
STRUCTURAL	LUNDY & FRANKE ENGINEERING
MECHANICAL	MECHANICAL
ELECTRICAL	ELECTRICAL
PROVISIONS	PROVISIONS
MEASUREMENT	MEASUREMENT
DATE	05/23/24

LUNDY & FRANKE ENGINEERING
548 HEIMER ROAD PH. (210) 979-7900
SAN ANTONIO, TEXAS 78232 FX. (210) 979-7800
TX FIRM REG. #3388

WFAC Black Box Addition PKG 1

1801 Main, Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



DATE: 05/23/2024

SHAWN J. FRANKE
82639
LICENSED PROFESSIONAL ENGINEER

CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date


ISSUE FOR CONSTRUCTION
BUILDING NUMBER AB

SECTION

S-303

ISSUE FOR CONSTRUCTION

0'
1'



1 SECTION
3/8" = 1'-0"

LA PROJECT NO.: 03/515-00
LA FILE NO.: WFAC-38blackbox Addition, Structural R23






ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-823-0123 P 210-823-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BLA ARCHITECTS
OWNER	ALAMO COLLEGES
DESIGNER	T. J. B. B. B.
LANDSCAPE	LANDSCAPE
ROOF AND DRIP	T. J. B. B. B.
STRUCTURAL	LUNDY & FRANKE ENGINEERING
MECHANICAL	LUNDY & FRANKE ENGINEERING
ELECTRICAL	LUNDY & FRANKE ENGINEERING
PLUMBING	LUNDY & FRANKE ENGINEERING
MECHANICAL	LUNDY & FRANKE ENGINEERING
MECHANICAL	LUNDY & FRANKE ENGINEERING



WFAC Black Box Addition PKG 1

1801 Marlin Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION




CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER AB

SECTION
S-304

ISSUE FOR CONSTRUCTION

0'
1'



1 SECTION
1/2" = 1'-0"

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-38blackbox Addition, Structural R23





ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-823-0123 P 210-823-5578 F TX Firm BR 1606	
ASSOCIATE ARCHITECT	BA ARCHITECTS
OWNER	ALAMO COLLEGES
DESIGNER	ALAMO COLLEGES
LANDSCAPE	ALAMO COLLEGES
ROSE AND DESIGN	ALAMO COLLEGES
STRUCTURAL	LUNDY & FRANKE ENGINEERING
MEE	LUNDY & FRANKE ENGINEERING
MEP	LUNDY & FRANKE ENGINEERING
PROVISION	LUNDY & FRANKE ENGINEERING
BEAM PROFESSIONALS	LUNDY & FRANKE ENGINEERING
MEASUREMENT	LUNDY & FRANKE ENGINEERING
CONSTRUCTION	LUNDY & FRANKE ENGINEERING



WFAC Black Box Addition PKG 1

1801 Mathis Luther King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date


ISSUE FOR CONSTRUCTION

BUILDING NUMBER AB


SECTION
S-306

ISSUE FOR CONSTRUCTION


LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-Blackbox Addition Structural R23



3 SECTION
3/4" = 1'-0"



2 SECTION
3/4" = 1'-0"



1 SECTION
3/4" = 1'-0"




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-5578 F TX Firm BR 1606	
ASSOCIATE ARCHITECT	MAX ARCHITECTS
CONTRACTOR	CON
DESIGNER	T.J. BOGGS
LANDSCAPE	CON
ROOF AND DRIP	T.J. BOGGS
STRUCTURAL	LUNDY & FRANKE ENGINEERING
MECHANICAL	CON
ELECTRICAL	CON
PLUMBING	CON
MECHANICAL	CON
MECHANICAL	CON
MECHANICAL	CON



WFAC Black Box Addition PKG 1

1801 Mathis Luther King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION




CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE	230462	
2024/05/23		
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	AB	


SECTIONS & DETAILS

S-309


1st FLOOR CONCRETE JOIST SCHEDULE															
MARK	SIZE			MAIN REINFORCING						STIRRUPS			REMARKS		
	W	D	SECT.	SPCG.	TOP BARS		BOTTOM BARS		TOP BARS AT SUPPORT		SIZE	NO. LEGS		SPACING AT EACH END OF JOIST	
					REINF.	TYP.	REINF.	TYP.	REINF.	TYP.	SUPP.				
J1	6	20		6'-0"	2-#6	T2	1-#8	B6	-	-	-	#4	10	11" O.C.	
J2	6	20		6'-0"	1-#8	T3	1-#8	B3	-	-	-	#4	10	11" O.C.	
J3	6	20		6'-0"	1-#6	T1	1-#6	B1	-	-	-	#4	8	11" O.C.	



1 DETAIL TYP. REINF. @ SLAB DROP SCALE: 3/4" = 1'-0"



2 DETAIL TYP. SLAB REINF. @ ACCESS HATCH SCALE: 3/4" = 1'-0"



3 DETAIL TYP. SLAB SECT. @ FLR. DROP SCALE: 3/4" = 1'-0"



4 DETAIL TYP. REINF. @ SLAB DROP SCALE: 3/4" = 1'-0"




5 DETAIL TYP. SECT. @ REINF. BM. SCALE: 3/4" = 1'-0"




6 DETAIL TYP. SECT. @ INT. BM. SCALE: 3/4" = 1'-0"


7 DETAIL TYP. ALLOWABLE CONDUIT PLACEMENT SCALE: 3/4" = 1'-0"




8 DETAIL TYP. SECT. @ REINF. BM. SCALE: 3/4" = 1'-0"




9 DETAIL TYP. SECT. @ INT. BM. SCALE: 3/4" = 1'-0"




10 DETAIL TYP. SLAB REINF. @ ACCESS HATCH SCALE: 3/4" = 1'-0"



11 DETAIL TYP. SLAB SECT. @ FLR. DROP SCALE: 3/4" = 1'-0"



12 DETAIL TYP. REINF. @ SLAB DROP SCALE: 3/4" = 1'-0"



13 DETAIL TYP. SECT. @ REINF. BM. SCALE: 3/4" = 1'-0"


- CONCRETE JOIST NOTES:**
- CJ-1 STEEL PAN-JOIST FORMS SHALL BE SPACED SO THAT JOISTS IN ADJACENT SPANS ARE IN EXACT ALIGNMENT UNLESS SHOWN OTHERWISE. NARROWER WIDTH FORMS SHALL BE COORDINATED WITH BASIC SPACING WHERE MAKE-UPS ARE REQUIRED.
 - CJ-2 WHERE STIRRUPS ARE SCHEDULED, (1) 6-LEG LADDER STIRRUP ASSEMBLY WITH VERTICAL LEGS AT 11" O.C. IS THE MINIMUM. IF SCHEDULE CALLS FOR MORE THAN 6 LEGS, USE A COMBINATION OF LADDER STIRRUP ASSEMBLIES TO PROVIDE REQUIRED NUMBER OF LEGS AT SPACING SCHEDULED.
 - CJ-3 JOIST TOP BARS SHALL BE SUPPORTED ON 1" DIA. X 1'-0" SUPPORT BARS PLACED ON 3/4" BAR CHAIRS ACROSS PAN FORMS AT 4'-0" O.C. TIED TO STIRRUPS BEGINNING AT FIRST LEG.
 - CJ-4 BEAM STEEL SHALL HAVE CLEARANCE OF 1-1/2" TO STIRRUPS AT BOTTOM AND SIDES BUT 2-1/2" AT TOP. JOIST STEEL SHALL HAVE CLEARANCE OF 1-1/2". THEREFORE, REINFORCEMENT SHALL BE PLACED IN THE FOLLOWING SEQUENCE:
 1. PLACE ALL BEAM BARS.
 2. PLACE BOTTOM JOIST BARS.
 3. PLACE SUPPORT BARS (NOTE CJ-3).
 4. PLACE TOP JOIST BARS.
 5. PLACE EXTRA SLAB BARS (NOTE CJ-7).
 6. PLACE WELDED WIRE FABRIC.
 - CJ-5 REINFORCE SLAB WITH 4x4-W3.5x3.5 WELDED WIRE FABRIC, LAPPED 1-1/2 MESHES AT SPLICES. DRAPE OVER TOP JOIST BARS AND TIE DOWN SECURELY IN BOTTOM OF SLAB MIDWAY BETWEEN JOISTS. 3/4" OFF BOTTOM WITH BAR CHAIRS AND TIED TO FROM AT 24" O.C. MESH SHALL EXTEND OVER THE ENTIRE WIDTH OF BEAMS.
 - CJ-6 WHERE FLOOR DROPS (DEPRESSIONS) OCCUR, ADJUST PAN FORMS SO THAT SLAB THICKNESS IS MAINTAINED AS SHOWN IN DETAILS.
 - CJ-7 WHERE JOIST RUN PARALLEL TO BEAMS OR WALLS, PROVIDE #3 DOWELS AT 2'-0" O.C. AT EDGE BEAMS ONLY. (SEE DETAIL).
 - CJ-8 UNLESS SPECIFICALLY SHOWN ON FRAMING PLANS, JOISTS SHALL NOT BE INTERRUPTED OR REDUCED IN CROSS SECTIONAL AREAS WITHOUT ENGINEER'S APPROVAL.
 - CJ-9 IF VERTICAL MECHANICAL SLEEVE PROJECTS INTO A JOIST BY MORE THAN 1-1/2", WIDEN JOIST BY USING NEXT SMALLER PAN WIDTH FOR A DISTANCE OF 4'-0" BOTH SIDES OF SLEEVE AND FIELD DRAPE BARS AROUND SLEEVES (NO TORCHING).
 - CJ-10 CONDUITS IN 4-1/2" SLABS SHALL NOT BE LARGER THAN 1" DIAMETER, WHERE CONDUIT IS PARALLEL (OR NEARLY PARALLEL) TO JOIST, DO NOT LOCATE IN CENTER THIRD OF SLAB SPAN.
 - CJ-11 PROVIDE 6" WIDE BRIDGING JOIST WHERE INDICATED "BJ" ON PLAN. REINFORCE WITH 1-#6 CONTINUOUS TOP AND BOTTOM AND ANCHOR INTO TERMINAL BEAMS WITH #6 X 5'-0" CORNER BAR TOP AND BOTTOM.
 - CJ-12 WHERE PARTITIONS RUNNING PARALLEL TO JOISTS ARE DESIGNATED BY THE SYMBOL ON THE FRAMING PLAN, OR NOTED ON ARCHITECTURAL DRAWINGS, ADD #4 X 6'-0" AT 9" O.C. FOR ENTIRE LENGTH OF JOIST SPAN, IN BOTTOM OF SLAB ON 3/4" BAR CHAIRS, RUNNING PERPENDICULAR TO JOISTS FROM JOIST CENTERLINE TO JOIST CENTERLINE.



ARCHITECT SAN ANTONIO
 PBK Architects, Inc.
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-820-0123 P
 210-829-5578 F
 TX Firm BR 1606

ENGINEERING
LUNDY & FRANKE
 588 HEIMER ROAD
 SAN ANTONIO, TEXAS 78232
 PH 210-979-7900
 TX FIRM REG. #3388

WFAC Black Box Addition PKG 1



CLIENT Alamo Colleges
 DATE 2024/05/23 PROJECT NUMBER 230462


No.	Description	Date

ISSUE FOR CONSTRUCTION
 BUILDING NUMBER AB

CONC. JOIST SCHED,
 NOTES & DETAILS

S-402

ISSUE FOR CONSTRUCTION



GENERAL SITE DEMOLITION NOTES

- DEMOLITION PLANS INDICATE SOME OF THE SCOPE OF WORK INVOLVED FOR THE DEMOLITION PHASE OF THIS PROJECT. CONTRACTOR SHALL REVIEW ALL SHEETS FOR ADDITIONAL DEMOLITION SCOPE.
- CONTRACTOR SHALL VERIFY EXISTING SITE AND BUILDING CONDITIONS AND DIMENSIONS IN THE FIELD PRIOR TO DEMOLITION ACTIVITIES AND WORK.
- CONTRACTOR SHALL NOTIFY ARCHITECT OF ANY DISCREPANCIES IN WRITING.
- CONTRACTOR SHALL NOTIFY ARCHITECT AND OWNER OF ANY POSSIBLE ASBESTOS CONTAINING MATERIALS DISCOVERED BEFORE PROCEEDING WITH WORK. PROTECT INTERIOR CONSTRUCTION TO REMAIN DURING DEMOLITION AND CONSTRUCTION.
- CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS BEFORE COMMENCING WORK.
- AFTER AWARD OF THE CONTRACT, CHANGE ORDER REQUESTS FOR ADDITIONAL MONEY WILL NOT BE APPROVED IF THE WORK COULD HAVE BEEN ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR.
- CONTRACTOR SHALL NOT SCALE DRAWINGS.
- CONTRACTOR SHALL PROVIDE ALL NECESSARY TEMPORARY SHORING, TEMPORARY BRACING, AND OR TEMPORARY SUPPORTS AS REQUIRED TO MAINTAIN STRUCTURAL INTEGRITY OF EXISTING STRUCTURE TO REMAIN AND OR EXISTING BUILDING ELEMENTS TO REMAIN.
- CONTRACTOR IS TO VERIFY THE EXACT LOCATION OF ALL EXISTING UTILITIES PRIOR TO DEMOLITION ACTIVITIES AND WORK.
- CONTRACTOR SHALL REMOVE TRASH AND DEBRIS REGULARLY AS NECESSARY TO ELIMINATED INTERFERENCE WITH ROADS, STREET, WALKS, AND ALL OTHER ADJACENT FACILITIES.
- CONTRACTOR SHALL REMOVE TRASH AND DEBRIS FROM THE SITE ON A DAILY BASIS.
- CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTION OF TEMPORARY DUST AND OR SOUND PARTITION BETWEEN CONSTRUCTION AREA AND AREAS NOT IN SCOPE AS NECESSARY. DEMOLITION ACTIVITIES SHALL BE PERFORMED SO AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY AND OCCUPANTS (I.E. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST).
- CONTRACTOR SHALL REPAIR, REPLACE, OR PATCH EXISTING BUILDINGS, DRIVEWAYS, SIDEWALKS, CANOPIES, AND OR PARKING AREAS DAMAGED, MODIFIED, AND OR DISTURBED BY DEMOLITION WORK AT NO COST TO THE OWNER.
- ALL EXISTING EQUIPMENT THAT REMAINS SHALL BE PROTECTED DURING DEMOLITION AND OR CONSTRUCTION TO PREVENT DAMAGE. ANY DAMAGE TO REMAINING EXISTING EQUIPMENT SUSTAINED DURING DEMOLITION AND OR CONSTRUCTION SHALL BE EQUIVALENTLY REPLACED OR EQUIVALENTLY REPAIRED AT NO COST TO THE OWNER.
- CONTRACTOR SHALL PROVIDE TRAFFIC HANDLING MEASURES TO PROTECT THE GENERAL PUBLIC AT ALL TIMES, AS NECESSARY AND AS REQUIRED BY AUTHORITIES HAVING JURISDICTION.
- DO NOT INTERRUPT EXISTING UTILITIES, EXCEPT WHEN AUTHORIZED IN WRITING BY AUTHORITIES HAVING JURISDICTION. PROVIDE TEMPORARY SERVICES DURING INTERRUPTIONS TO EXISTING UTILITIES AS ACCEPTABLE TO AUTHORITIES HAVING JURISDICTION.
- WHEN UTILITY SERVICES ARE REQUIRED TO BE REMOVED, RELOCATED, OR ABANDONED, PROVIDE BYPASS CONNECTIONS TO MAINTAIN CONTINUITY OF SERVICE BEFORE PROCEEDING WITH DEMOLITION.
- CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES INCLUDING BUT NOT LIMITED TO THE FOLLOWING: ELECTRIC, GAS, WATER, TELEPHONE, STORM SEWER, AND SANITARY SEWER FOR FIELD LOCATION OF ALL UNDERGROUND AND OVERHEAD UTILITY LINES. PRIOR TO COMMENCEMENT OF ANY DEMOLITION WORK, CONTRACTOR SHALL IDENTIFY ALL ELECTRICAL CIRCUITS SERVICING THE AREA INVOLVED WITH THIS DEMOLITION. THOSE CIRCUITS SHALL THEN BE LOCKED OUT AND TAGGED OUT IF THEY DO NOT SERVICE ANY OF THE REMAINING BUILDING. THOSE CIRCUITS WHICH ARE IDENTIFIED TO SERVICE BOTH THE AREA TO BE DEMOLISHED AND THE REMAINING BUILDING SHALL BE SPLIT SO AS TO KILL ALL ELECTRICAL POWER TO THE AREA TO BE DEMOLISHED WHILE MAINTAINING POWER TO THE REMAINDER OF THE BUILDING.
- CONTRACTOR SHALL RELOCATE UTILITIES AND EQUIPMENT AS REQUIRED TO ACCOMMODATE NEW HVAC, ELECTRICAL, PLUMBING, AND TECHNOLOGY REQUIREMENTS FOR NEW WORK.
- PROTECT EXISTING SITE ELEMENTS AND EXISTING LANDSCAPING TO REMAIN. PROTECTION SHALL INCLUDE BUT NOT BE LIMITED TO EXISTING TREES AND OTHER EXISTING VEGETATION INDICATED TO REMAIN IN PLACE AGAINST UNNECESSARY CUTTING, BREAKING, OR SKINNING OF ROOTS, SKINNING OR BRUISING OF BARK, SMOTHERING OF TREES BY STOCKPILING CONSTRUCTION MATERIAL OR EXCAVATED MATERIAL WITHIN DRIP LINES.
- CONTRACTOR SHALL REGRADE AND HYDROMULCH AREAS AFFECTED BY DEMOLITION.
- OWNER HAS RIGHT OF FIRST REFUSAL OF ALL ITEMS REMOVED AS PART OF THE SCOPE OF WORK, WHETHER IDENTIFIED AS SALVAGE OR NOT.
- NOTIFY THE BUILDING OWNER OF ANY MATERIALS, FIXTURES, ETC. TO BE REMOVED THAT ARE DESIRED SALVAGEABLE. TURN OVER ANY REQUESTED ITEMS TO THE BUILDING OWNER IN GOOD AND CLEAN CONDITION.
- ALL FURNITURE WILL BE REMOVED OR RELOCATED BY THE OWNER AS NECESSARY PRIOR TO THE DEMOLITION WORK OF THIS PROJECT. CONTRACTOR SHALL COORDINATE WITH OWNER AS REQUIRED.




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-820-0578 F TX Firm BR 1608	
ARCHITECT	PBK ARCHITECTS
DESIGNER	TRAVIS BROWN
LANDSCAPE	TRAVIS BROWN
ENGINEER	TRAVIS BROWN
INSPECTOR	TRAVIS BROWN
LANDSCAPE	TRAVIS BROWN
MECHANICAL	TRAVIS BROWN
ELECTRICAL	TRAVIS BROWN
PLUMBING	TRAVIS BROWN
CONSTRUCTION	TRAVIS BROWN
DATE	6/14/2024

WFAC Black Box Addition PKG 1

1801 Marlin Luther King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE	230462	
2024/06/14		
DRAWING HISTORY		
No.	Description	Date








DEMOLITION ARCHITECTURAL SITE PLAN

ASD101

SITE DEMOLITION PLAN LEGEND

- EXISTING BUILDING
- DEMO ENTIRE FACILITY (FOUNDATION, STRUCTURE, WALLS, ROOFS)
- DEMO CHAINLINK FENCE
- DEMO ORNAMENTAL FENCE

06 DEMOLITION SITE PLAN
1" = 20'-0"



GENERAL ARCH SITE PLAN NOTES

- REFER TO CIVIL DOCUMENTS.
- COORDINATE ALL SPOT ELEVATIONS AND DIMENSIONS WITH CIVIL, LANDSCAPE, AND/OR STRUCTURAL DOCUMENTS.
- PROVIDE POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 1% MINIMUM, 2% MAXIMUM AT ALL EXTERIOR PAVED PEDESTRIAN AREAS, INCLUDING BUT NOT LIMITED TO SIDEWALKS, PATIOS, STAIRS, PAVING, U.N.O.
- PROVIDE AND INSTALL POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 5% FOR A HORIZONTAL DISTANCE OF 10 FEET AT ALL EXTERIOR NON-PAVED AREAS U.N.O.
- REFER TO CIVIL DOCUMENTS FOR CONCRETE SIDEWALK EXPANSION JOINTS AND CONCRETE SIDEWALK CONTROL JOINTS.
- VERIFY AND CONFIRM ALL JOINT LAYOUTS AT ALL CONCRETE SIDEWALKS WITH ARCHITECT PRIOR TO POURING OF CONCRETE.
- PROVIDE AND INSTALL CONCRETE SIDEWALK EXPANSION JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT 50 FEET ON-CENTER MAX. U.N.O.
- PROVIDE AND INSTALL CONCRETE SIDEWALK CONTROL JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT DISTANCES EQUIVALENT TO SIDEWALK WIDTH, BUT NOT TO EXCEED 10 FEET ON-CENTER MAX.
- VERIFY ALL SITE SIGNAGE LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION OF SITE SIGNAGE.

KEYNOTE LEGEND

NUMBER	DESCRIPTION
04 05 00 CDP	CAVITY DRAINAGE MATERIAL
04 05 00 TIE	TIE SYSTEM
04 05 00 WWV	WICKING WEEP
04 20 00 BK1	BRICK TYPE 1 - FIELD
04 20 00 BK2	BRICK TYPE 2 - WHITE ACCENT
04 20 00 CBB	CMU BOND BEAM
04 20 00 CUB (R)	8" CMU - RUNNING BOND



ARCH SITE PLAN LEGEND

- EXISTING BUILDING
- NOT IN SCOPE
- NEW BUILDING / ADDITION
- GRASS
- SIDEWALK
- TOP CAST CONCRETE, RE. LANDSCAPE
- SALT FINISH CONCRETE, RE. LANDSCAPE



ARCHITECT: PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-820-0578 F
TX Firm BR 1608


WFAC Black Box Addition PKG 1
1801 Marlin Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION




CLIENT: Alamo Colleges		
DATE: 2024/06/14	PROJECT NUMBER: 230462	
DRAWING HISTORY		
No.	Description	Date
1	AS1 #1 - CITY & OWNER COMMENTS	6-14-2024

ISSUE FOR CONSTRUCTION
BUILDING NUMBER: 1
ARCHITECTURAL ENLARGED SITE PLANS


AS401




30 UNDERGROUND SUMP PUMP DETAIL
 1/4" = 1'-0"




29 AREAWAY DETAIL
 3/4" = 1'-0"



18 UNDERFLOOR ACCESS DOOR
 3/4" = 1'-0"



13-14 UNDERFLOOR ACCESS DOOR
 3/4" = 1'-0"




06 CRAWLSPACE
 1/8" = 1'-0"

GENERAL ARCH PLAN NOTES

- DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS TAKE PRECEDENCE. CONTACT ARCH IF CLARIFICATION IS NECESSARY IN ORDER TO DETERMINE THE INTENT OF THE CONTRACT DOCUMENTS.
- DRAWINGS NOTED AS "N.T.S." OR "NTS" ARE NOT TO SCALE.
- ALL DIMENSIONS ARE TO STRUCTURAL COLUMN LINES OR THE SURFACE OF PARTITION ASSEMBLY U.N.O.
- FIELD VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS BEFORE COMMENCING WORK. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO PROCEEDING WITH AFFECTED WORK.
- NOTES OR DIMENSIONS NOTED AS "TYPICAL" OR "TYP." OR "TYP" SHALL APPLY TO CONDITIONS THAT ARE THE SAME, OR SIMILAR.
- DIMENSIONS NOTED AS "FIELD VERIFY" OR "V.I.F." OR "V.I.P." SHALL BE MEASURED AND CONFIRMED AT THE PROJECT SITE BY THE CONTRACTOR AND REVIEWED WITH THE ARCH. BEFORE INCORPORATING INTO THE WORK.
- DIMENSIONS NOTED AS "CLEAR" OR "CLEAR INSIDE" OR "CLR" REQUIRE SPECIFIC COORDINATION AMONG DISCIPLINES AND OR MANUFACTURERS.
- REFER TO PARTITION TYPES ON A-800 SERIES SHEETS.
- DIMENSIONS NOTED AS "CLEAR" OR "CLEAR INSIDE" OR "CLR" REQUIRE SPECIFIC COORDINATION AMONG DISCIPLINES AND OR MANUFACTURERS.
- REFER TO PARTITION TYPES ON A-800 SERIES SHEETS.
- ALL INTERIOR PARTITIONS THIS SHEET, EXCEPT FOR FURR-OUT PARTITIONS, SHALL BE PARTITION TYPE _38_ U.N.O.
- ALL INTERIOR FURR-OUT PARTITIONS THIS SHEET SHALL BE PARTITION TYPE _F3_ U.N.O.
- ADJOIN FINISHED FACE OF WALLS WHERE WALL PARTITIONS OF DIFFERING THICKNESS ABUT AND OR ADJOIN IN THE SAME PLANE.
- PROVIDE AND INSTALL CONTINUOUS REVEAL TRIM AT JOINT WHERE GYPSUM BOARD WALL PARTITIONS ABUT AND OR ADJOIN MASONRY WALL PARTITIONS IN THE SAME PLANE.
- ALL INTERIOR CMU OUTSIDE CORNERS SHALL HAVE BULLNOSE U.N.O.
- ALL DOORS SHALL BE SET 4 INCHES OFF THE ADJACENT PERPENDICULAR WALL ON THE HINGE SIDE OF THE DOOR U.N.O. NOTIFY ARCH. OF ANY DOOR-RELATED CONFLICTS, INCLUDING BUT NOT LIMITED TO CONFLICTS CONCERNING ACCESSIBILITY STANDARDS.
- ALL DOOR THRESHOLDS AT ALL EXTERIOR DOORS SHALL BE SET IN FULL BED OF SEALANT.
- COORDINATE ALL ROOF DRAIN LEADER LOCATIONS WITH FLOOR PLAN PRIOR TO FLOOR SLAB CONSTRUCTION.
- ALL FLOOR SLOPES TO FLOOR DRAINS SHALL NOT EXCEED 1:48.
- PROVIDE AND INSTALL SELF-LEVELING UNDERLAYMENT WHERE UNEVEN FLOOR SLAB EXISTS PRIOR TO INSTALLATION OF FLOOR FINISHES.
- COORDINATE HOUSEKEEPING PAD LOCATIONS AND DIMENSIONS WITH EQUIPMENT TO BE INSTALLED.
- ALL FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS U.N.O.
- ALL FLOOR FINISH MATERIAL CHANGES SHALL HAVE REDUCER STRIPS.
- ALL REQUIRED ACCESSIBLE CLEARANCES FOR ALL ITEMS, INCLUDING BUT NOT LIMITED TO ALL COUNTER TOPS, ALL PLUMBING FIXTURES, ALL DRINKING FOUNTAINS, ALL ELECTRIC WATER COOLERS, ALL LAVATORIES, ALL URINALS, ALL TOILETS SHALL BE STRICTLY ENFORCED.
- APPLY BITUMINOUS COATING TO ALL CONCEALED STRUCTURAL STEEL MEMBERS AT ALL EXTERIOR CANOPY LOCATIONS.
- REFER TO OTHER DISCIPLINE DOCUMENTS FOR ADDITIONAL SCOPE OF WORK.

FLOOR FINISH LEGEND




ARCHITECT PBK Architects, Inc.
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-829-0123 P
 210-829-0578 F
 TX Firm BR 1608

ARCHITECT BA & ARCHITECTS
 1100 S. W. Loop West
 Suite 100
 San Antonio, TX 78205
 210-442-0000
 LUNY & FRANKS ENGINEERING
 1100 S. W. Loop West
 Suite 100
 San Antonio, TX 78205
 210-442-0000
 MEAN PROFESSIONALS
 1100 S. W. Loop West
 Suite 100
 San Antonio, TX 78205
 210-442-0000

WFAC Black Box Addition PKG 1

1801 Mathis Luther King Dr.,
 San Antonio, TX 78203

ISSUE FOR CONSTRUCTION




CLIENT		Alamo Colleges	
DATE	2024/06/14	PROJECT NUMBER	230462
DRAWING HISTORY			
No.	Description	Date	
ISSUE FOR CONSTRUCTION			
BUILDING NUMBER	1		
CRAWLSPACE FLOOR PLAN - COMPOSITE			

ISSUE FOR CONSTRUCTION

File Path: Autodesk Docs://Alamo_CS_230462_Al Philip College WBB Add#E23 WFAC - Blackbox Addition - A23.rvt

CHECKED BY:
Checker
DRAWN BY:
Author
Plot Stamp:
6/13/2024 12:25:09 PM

5
1



DEMO SITE PLAN GENERAL NOTES:

- COORDINATE ROUTING FOR ALL UNDERGROUND ELECTRICAL BRANCH CIRCUITS AND FEEDERS WITH OTHER DISCIPLINES PRIOR TO TRENCHING.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING UTILITIES CAUSED BY INSTALLATION OF NEW WORK.

SITE PLAN KEYED NOTES:



- EXISTING ELECTRICAL MANHOLE.
- EXISTING ELECTRICAL MANHOLE SHALL BE DEMOLISHED AND RELOCATED.
- EXISTING UNDERGROUND ELECTRICAL DUGBANK WITH 4 EXISTING CONDUITS TO BE REROUTED FOR NEW BLACK BOX EXPANSION.
- CONTRACTOR TO VERIFY NEW CONSTRUCTIONS DOES NOT OVERLAP EXISTING PARKING LOT LIGHTING. IF NEW CONSTRUCTIONS OVERLAPS EXISTING FEEDER FOR PARKING LOT LIGHTING, EXISTING FEEDERS FOR SITE LIGHTING SHALL BE RELOCATED.
- EXISTING CONDENSING UNIT SHALL BE RELOCATED. DISCONNECT AND CONDUCTORS SHALL BE REROUTED. UTILIZE EXISTING CIRCUIT. COORDINATE EXACT LOCATION WITH MECHANICAL DRAWINGS.
- EXISTING DISTRIBUTION MAIN SERVICE DISCONNECT DP-6 FOR ADJACENT WATSON FINE ARTS BUILDING.
- EXISTING CONDUITS FROM DP-6 TO WATSON'S FINE ARTS BUILDING SHALL BE RELOCATED TO ACCOMMODATE NEW BUILDING. CONTRACTOR SHALL VERIFY PATH WAY AND RELOCATED CONDUITS AND CONDUCTORS TO NEW AVAILABLE LOCATION WITHOUT IMPEDE ANY OTHER SERVICES.
- EXISTING UTILITY TRANSFORMER FOR WATSON FINE ARTS.
- EXISTING PARKING LOT FIXTURES SHALL BE DEMOLISHED. CONTRACTOR SHALL PRESERVE CIRCUIT RUN FOR ANY EXISTING FIXTURES REMAINING OR TIED TO DEMOLISHED FIXTURES.
- EXISTING PEDESTRIAN LOT FIXTURES SHALL BE RELOCATED. CONTRACTOR SHALL PRESERVE CIRCUIT RUN FOR ANY EXISTING FIXTURES REMAINING OR TIED TO DEMOLISHED FIXTURES.



ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-5578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	B&A ARCHITECTS 1100 N. LOOP WEST SUITE 1000 SAN ANTONIO, TEXAS 78207 210-224-1100
ENGINEER	LEAF ENGINEERS 1801 Main Luther King Dr., San Antonio, TX 78203
LANDSCAPE	LANDSCAPE 1111 W. LOOP WEST SUITE 1000 SAN ANTONIO, TEXAS 78207 210-224-1100
MECHANICAL	LUNY & FRANK ENGINEERING 1111 W. LOOP WEST SUITE 1000 SAN ANTONIO, TEXAS 78207 210-224-1100
ELECTRICAL	LEAF ENGINEERS 1801 Main Luther King Dr., San Antonio, TX 78203
PLUMBING	LEAF ENGINEERS 1801 Main Luther King Dr., San Antonio, TX 78203
MECHANICAL	LEAF ENGINEERS 1801 Main Luther King Dr., San Antonio, TX 78203



WFAC Black Box Addition PKG 1




CLIENT	Alamo Colleges	
DATE	06/14/2024	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1
DEMO SITE POWER PLAN

EDS-101

5
1



- ELECTRICAL ONE-LINE DIAGRAM NOTES:**
- # INDICATES GENERAL NOTE.
 - Ⓢ INDICATES KEYED NOTE.
1. UNLESS NOTED OTHERWISE, ALL TRANSFORMERS TO BE 480/208/120 VOLT 3P, 4W.
 2. PROVIDE THRU-FEED LUGS FOR ALL MULTI-SECTION PANELBOARDS.
 3. REFERENCE ONE-LINE DIAGRAM.
 4. 1#6 G, 3/4"C.
 5. SURGE PROTECTIVE DEVICE, RE: DIVISION 26 SPECIFICATIONS FOR ADDITIONAL INFORMATION.
 6. PER LOCAL NEC STANDARDS.
 7. PROVIDE (2) 3-1/2" CONDUITS WITH PULL STRING(S) STUBBED 5' OUTSIDE OF THE MAIN BUILDING FOR FUTURE USE.

ALUMINUM FEEDER SCHEDULE				
TAG NUMBER	CONDUCTOR QUANTITY AND SIZE	CONDUIT SIZE	SETS	COMMENTS
200	3#250, 1#4G	2"	1	
200N	4#250, 1#4G	2 1/2"	1	
225	3#300, 1#2G	2 1/2"	1	
225N	4#300, 1#2G	3"	1	
250	3#350, 1#2G	2 1/2"	1	
250N	4#350, 1#2G	3"	1	
300	3#500, 1#2G	3"	1	
300N	4#500, 1#2G	3"	1	
400	3#250, 1#1G	2 1/2"	2	
400N	4#250, 1#1G	2 1/2"	2	
600	3#500, 1#2OG	3"	2	
600N	4#500, 1#2OG	3 1/2"	2	
800	3#400, 1#3OG	3"	3	
800N	4#400, 1#3OG	3"	3	
1200	3#500, 1#3OG	3"	4	
1200N	4#500, 1#3OG	3 1/2"	4	

FEEDER SCHEDULE				
TAG NUMBER	CONDUCTOR QUANTITY AND SIZE	CONDUIT SIZE	SETS	COMMENTS
30N	4#10, 1#10G	1"	1	
50N	4#6, 1#10G	1"	1	
60N	4#6, 1#10G	1"	1	
100	3#1, 1#6G	1 1/2"	1	
100N	4#1, 1#6G	1 1/2"	1	
125	3#1, 1#6G	1 1/2"	1	
125N	4#1, 1#6G	2"	1	
150	3#1/0, 1#6G	1 1/2"	1	
150N	4#1/0, 1#6G	2"	1	
175	3#2/0, 1#6G	2"	1	
175N	4#2/0, 1#6G	2"	1	
200	3#3/0, 1#6G	2"	1	
200N	4#3/0, 1#6G	2"	1	
225	3#4/0, 1#4G	2"	1	
225N	4#4/0, 1#4G	2 1/2"	1	
250	3#250, 1#4G	2 1/2"	1	
250N	4#250, 1#4G	3"	1	
300	3#350, 1#4G	3"	1	
300N	4#350, 1#4G	3"	1	
400	3#3/0, 1#3G	2"	2	
400N	4#3/0, 1#3G	2"	2	
400S	4#500	3 1/2"	1	
600	3#350, 1#1G	3"	2	
600N	4#350, 1#1G	3"	2	
600S	4#350	3"	2	
800	3#500, 1#1OG	3"	2	
800N	4#500, 1#1OG	3 1/2"	2	
800S	4#500	3 1/2"	2	
1000	3#400, 1#2OG	3"	3	
1000N	4#400, 1#2OG	3"	3	
1000S	4#400	3"	3	
1200	3#250, 1#3OG	3"	4	
1200N	4#250, 1#3OG	3"	4	
1200S	4#250	3"	4	
1600S	4#400	3"	5	
2000S	4#400	3"	6	
2500S	4#500	3 1/2"	7	
3000S	4#500	3 1/2"	8	
4000S	4#500	3 1/2"	11	



TRANSFORMER FEEDER SCHEDULE				
TAG NUMBER	CONDUCTOR QUANTITY AND SIZE	CONDUIT SIZE	SETS	COMMENTS
P15	3#10, 1#10G	3/4"	1	
S15	4#6, 1#6G	1 1/2"	1	
K15	3#4, 1#6N, 1#6G	1 1/4"	1	
G15	1#6G	1/2"	1	
P15	2#6, 1#10G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
S15	3#4, 1#6G	1 1/2"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G15	1#6G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P25	2#6, 1#10G	1"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
D25	3#1, 1#6G	1 1/2"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G25	1#6G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P30	3#6, 1#10G	3/4"	1	
S30	4#1, 1#6G	1 1/2"	1	
K30	3 #1/0, 1#2/0N, 1#6G	2"	1	
G30	1#6G	1/2"	1	
P37	2#1, 1#6G	1 1/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
D37	3#3/0, 1#4G	3"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G37	1#4G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P45	3#4, 1#6G	1"	1	
S45	4#1/0, 1#6G	1 1/2"	1	
K45	3#2/0, 1#250, 1#4G	2"	1	
G45	1#6G	1/2"	1	
P50	2#1, 1#6G	1 1/4"	1	
S50	3#3/0, 1#3G	2"	1	
G50	1#3G	3/4"	1	
P75	3#1, 1#6G	1 1/2"	1	
S75	4#4/0, 1#2G	2 1/2"	1	
K75	3#4/0, 2#3/0N, 1#2G	2 1/2"	1	
G75	1#1/0G	1/2"	1	
P75	2#3/0, 1#6G	2"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
S75	3#3/0, 1#4G	2"	2	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G75	1#4G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P75A	3#1, 1#6G	1 1/2"	1	FOR 480 3Ø: 120/240 3Ø TRANSFORMERS
S75A	4#4/0, 1#2G	2 1/2"	1	FOR 480 3Ø: 120/240 3Ø TRANSFORMERS
G75A	1#2/0	1/2"	1	FOR 480 3Ø: 120/240 3Ø TRANSFORMERS
P112	3#2/0, 6G	2"	1	
S112	4#3/0, 1#10G	2"	2	
K112	3#4/0, 1#350N, 1#1/0G	2 1/2"	2	
G112	1#1/0G	3/4"	1	
P150	3#250, 1#4G	2 1/2"	1	
S150	4#350, 1#2OG	3"	2	
K150	3#350, 2#3/0N, 1#2/0G	3"	2	
G150	1#2/0G	3/4"	1	
P167	2#4/0, 1#2OG	2"	2	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
S167	3#350, 1#3OG	3"	3	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G167	1#3OG	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P225	3#500, 3#3G	3"	1	
S225	4#350, 1#2OG	3"	1	
K225	3#350, 2#4/0, 1#1G	3 1/2"	3	
G225	1#2OG	3/4"	1	



ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-5578 F
TX Firm BR 1608



WFAC Black Box Addition PKG 1
1801 Main Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION




CLIENT Alamo Colleges		PROJECT NUMBER 230462
DATE 06/14/2024		
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

ELECTRICAL RISER DIAGRAM

ISSUE FOR CONSTRUCTION



SITE PLAN GENERAL NOTES:

1. COORDINATE ROUTING FOR ALL UNDERGROUND ELECTRICAL BRANCH CIRCUITS AND FEEDERS WITH OTHER DISCIPLINES PRIOR TO TRENCHING.
2. UNLESS NOTED OTHERWISE ALL UNDERGROUND CONDUIT SHOWN ON THIS PLAN TO BE MINIMUM 1" IN SIZE.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING UTILITIES CAUSED BY INSTALLATION OF NEW WORK.

SITE PLAN KEYED NOTES:



- 1 EXISTING ELECTRICAL MANHOLE.
- 2 NEW UNDERGROUND EASEMENT FOR NEW PRIMARY POWER FOR UTILITY TRANSFORMER. FIELD VERIFY THAT SPARE CAPACITY IS AVAILABLE.
- 3 NEW 480277V 750KVA TRANSFORMER SHALL BE PROVIDED FROM ALAMO COLLEGES. CONTRACTOR SHALL COORDINATE EXACT LOCATION WITH ARCHITECTURAL PLANS PROVIDE (1) 1 1/2" CONDUIT FOR POWER.
- 4 NEW UNDERGROUND ROUTE FOR SECONDARY TO MAIN SERVICE DISCONNECT. PROVIDE (2) 3" CONDUITS FOR POWER.
- 5 NEW 480277V, 40 KW CUMMINS MODEL NUMBER: C40 N6 FOR FIRE PUMP.
- 6 NEW UNDERGROUND PATHWAY FROM GENERATOR TO 2ND FLOOR ATS IN MEZZAINE.
- 7 REROUTED PATHWAY FOR EXISTING UNDERGROUND DUCKSANK WITH 4 EXISTING CONDUITS. CONTRACTOR SHALL VERIFY EXACT PATHWAY OF EXISTING CONDUITS AND FEEDERS SIZES WITHIN EXISTING MANHOLES. CONTRACTOR SHALL COORDINATE NEW PATHWAY WITH ST. PHILLIPS UTILITY FACILITIES TO ENSURE PATHWAY CAN BE Routed.
- 8 RELOCATED CONDENSING UNIT AND ASSOCIATED DISCONNECT. COORDINATE WITH MECHANICAL FOR EXACT LOCATION.
- 9 EXISTING DISTRIBUTION MAIN SERVICE DISCONNECT DP-6 FOR ADJACENT WATSON FINE ARTS BUILDING.
- 10 EXISTING UTILITY TRANSFORMER FOR WATSON FINE ARTS.
- 11 PROPOSED NEW PATHWAY FOR RELOCATED EXISTING CONDUITS FROM DP-6. CONTRACTOR SHALL VERIFY WHERE CONDUITS ARE FED TO.
- 12 NEW LOCATION OF PEDESTRIAN POLES. COORDINATE EXACT LOCATION WITH ARCHITECTURAL DRAWINGS. UTILIZE EXISTING CIRCUIT IF AVAILABLE. IF CIRCUIT ISNT OBTAINABLE CONTRACTOR SHALL UTILIZE NEAREST AVAILABLE SPARE IN PANEL WITH IDENTICAL VOL TAGS.



ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	B&A ARCHITECTS 1100 N. LOOP WEST SUITE 1000 DALLAS, TEXAS 75201 214-760-1000
LANDSCAPE ARCHITECT	LANDSCAPE 1111 W. 14TH STREET SUITE 1000 DALLAS, TEXAS 75202 214-760-1000
MECHANICAL ENGINEER	LUNY & FRANK ENGINEERING 1111 W. 14TH STREET SUITE 1000 DALLAS, TEXAS 75202 214-760-1000
ELECTRICAL ENGINEER	MEAF PROFESSIONALS 1111 W. 14TH STREET SUITE 1000 DALLAS, TEXAS 75202 214-760-1000



WFAC Black Box Addition PKG 1
1801 Main Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	06/14/2024	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

SITE POWER PLAN

1 SITE POWER PLAN
SCALE: 1" = 20'-0"

PLUMBING ABBREVIATION SCHEDULE			
(A)	ITEM NOTED TO BE ABANDONED	KW	KILOWATTS
(D)	ITEM NOTED TO BE DEMOLISHED	L	LAVATORY
(E)	EXISTING ITEM	MAP	MASTER ALARM PANEL
(N)	NEW ITEM	MECH	MECHANICAL
(R)	ITEM NOTED TO BE RELOCATED	MH	MANHOLE
AAP	AREA ALARM PANEL	MS	MOP SINK
AAV	AUTOMATIC AIR VENT	NC	NORMALLY CLOSED
AFF	ABOVE FINISHED FLOOR	NIC	NOT IN CONTRACT
AP	ACCESS PANEL	NO	NORMALLY OPEN
BFF	BELOW FINISHED FLOOR	OF / CI	OWNER FURNISHED / CONTRACTOR INSTALLED
BFP	BACKFLOW PREVENTER	OF / OI	OWNER FURNISHED / OWNER INSTALLED
BOB	BOTTOM OF BEAM	OD	OVERFLOW DRAIN
BOP	BOTTOM OF PIPE	PV	POST INDICATOR VALVE
BTUH	BRITISH THERMAL UNITS PER HOUR	PRV	PRESSURE REDUCING VALVE
C / C	CUT AND CAP	RD	ROOF DRAIN
CFH	CUBIC FEET PER HOUR	RE	REFER TO
CFS	CUBIC FEET PER SECOND	RIC	ROUGH-IN AND CONNECT
CI	CAST IRON	RO	REVERSE OSMOSIS
CLG	CEILING	RP BFP	REDUCED PRESSURE BACKFLOW PREVENTER
CO	CLEANOUT	RPM	REVOLUTIONS PER MINUTE
CONN	CONNECTION	RVB	REFRIGERATOR VALVE BOX
CONT	CONTINUATION	SD	STORM DRAIN
DF	DRINKING FOUNTAIN	SF	SQUARE FEET
DPV	DRY PIPE VALVE	SIA	SERVICE SINK
DWG	DRAWING	SK	SINK
EA	EACH	TMV	THERMOSTATIC MIXING VALVE
EDF	ELECTRIC DRINKING FOUNTAIN	TOP	TOP OF PIPE
FCO	FLOOR CLEANOUT	TP	TRAP PRIMER
FD	FLOOR DRAIN	TYP	TYPICAL
FDV	FIRE DEPARTMENT VALVE	U	URNAL
FF	FINISHED FLOOR	UF	UNDERFLOOR
FHC	FIRE HOSE CABINET	UIS	UNDERSLAB
FL	FLOW LINE	VB	VACUUM BREAKER
FS	FLOOR SINK	VCT	VITRIFIED CLAY TILE
FT	FEET	VTR	VENT THRU ROOF
FU	FIXTURE UNIT	WC	WATER CLOSET
GC	GENERAL CONTRACTOR	WCO	WALL CLEANOUT
GPH	GALLONS PER HOUR	WH	WALL HYDRANT
GPM	GALLONS PER MINUTE	WMB	WASHING MACHINE BOX
HB	HOSE BIBB	YH	YARD HYDRANT
HP	HORSEPOWER	ZV	ZONE VALVE
IE	INVERT ELEVATION		

NOTES:
1. NOT ALL ABBREVIATIONS MAY BE USED ON THESE DRAWINGS.

PLUMBING SYMBOLS LEGEND			
DRAWINGS	DETAILS	ABV.	DESCRIPTION
		AV	ACID VENT
		AW	ACID WASTE
		CA	COMPRESSED AIR
		CW	COLD WATER
		(D)	DEMOLISHED PIPING OR EQUIPMENT
		D	CONDENSATE
		DSP	DRY SPRINKLER
		(E)	EXISTING PIPING OR EQUIPMENT
		F	FIRE
		G	NATURAL GAS
		GW	GREASE WASTE
		HW	HOT WATER
		HWR	HOT WATER RETURN
		OD	OVERFLOW DRAIN
		SD	STORM DRAIN
		SP	SPRINKLER
		SS	SANITARY SEWER
		V	VENT
			DIRECTION OF FLOW
			DROP IN PIPE
			RISE IN PIPE
			GATE VALVE
			BALL VALVE
			CHECK VALVE
			SUPERVISED VALVE WITH FLOW SWITCH
			PLUG VALVE / GAS COCK
			BUTTERFLY VALVE
			HOT WATER BALANCING VALVE
			PIPE UNION
			PRESSURE CONTROL VALVE
			3-WAY VALVE
			SOLENOID VALVE
			FLOW SWITCH
			PRESSURE GAUGE WITH GAUGE COCK
			THERMOMETER
		RD / ORD	ROOF DRAIN / OVERFLOW DRAIN
		FD	FLOOR DRAIN
		FS	FLOOR SINK
			T & P RELIEF VALVE
			STRAINER
		CO	END OF LINE CLEANOUT
		FCO	FLOOR CLEANOUT
		WCO	WALL CLEANOUT
			CAP
			FLEXIBLE CONNECTION
			NEW CONNECTION TO EXISTING PIPING


NOTES:
1. NOT ALL SYMBOLS MAY BE USED ON THESE DRAWINGS.

PLUMBING PIPE MATERIAL SCHEDULE		
PIPING SYSTEM	BELOW GRADE	ABOVE GRADE
STORM WATER	SCH 40 PVC	CAST IRON
SANITARY WASTE	SCH 40 PVC	CAST IRON
DOMESTIC WATER	TYPE 'K' COPPER	TYPE 'L' COPPER
NATURAL GAS	POLYETHYLENE PIPE W/ SLEEVE UNDER SLAB	SCH 40 BLACK STEEL
FIRE PROTECTION	SCH 40 BLACK STEEL	SCH 40 BLACK STEEL
COMPRESSED AIR	TYPE 'K' COPPER	SCH 40 GALVANIZED STEEL

WATER HAMMER ARRESTER SCHEDULE		
PIPE SIZE	CROSS FIXTURE UNITS	PDI STD.
1/2"	1-11	"A"
3/4"	12-32	"B"
1"	33-60	"C"
1-1/4"	61-113	"D"
1-1/2"	114-154	"E"
2"	155-330	"F"

NOTES:
1. AIR CHAMBERS OR SHOCK ARRESTORS SHALL BE PROVIDED TO ALL FIXTURE RUNOUT AND SHALL BE SIZED ACCORDING TO LOCAL PLUMBING CODE (HHS) & PDI. AIR CHAMBERS OR SHOCK ARRESTORS SHALL BE SIZED AND INSTALLED PER MANUFACTURER'S REQUIREMENTS. THE DEVICE SHALL HAVE LIFETIME WARRANTY AND BE INSTALLED WITHOUT REQUIRING ACCESS DOORS AND PANELS.

SLOPE OF HORIZONTAL DRAINAGE PIPE	
PIPE SIZE	MINIMUM SLOPE
2-1/2" OR LESS	1/4" PER FOOT
3" TO 6"	1/8" PER FOOT
8" OR LARGER	1/16" PER FOOT



PROJECT GENERAL NOTES


- ALL EQUIPMENT AND/OR SYSTEMS NOTED ON THE DRAWINGS TO REMAIN SHALL BE INSPECTED AND TESTED ON SITE TO CERTIFY WORKING CONDITION. A WRITTEN REPORT ON THE CONDITION OF ALL EQUIPMENT TO REMAIN, INCLUDING A COPY OF THE TEST RESULTS WITH RECOMMENDED REMEDIAL ACTIONS AND COSTS SHALL BE MADE BY THIS CONTRACTOR TO THE ARCHITECT/ENGINEER FOR REVIEW.
- THE PLUMBING WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE APPLICABLE CODES AS WELL AS ALL LOCAL REGULATIONS THAT MAY APPLY. IN CASE OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND A GOVERNING CODE OR ORDINANCE, THE MORE STRINGENT STANDARD SHALL APPLY.
- ALL PLUMBING WORK SHALL BE COORDINATED WITH ALL OTHER TRADES BEFORE PROCEEDING WITH THE INSTALLATION.
- INVERT ELEVATIONS AND EXACT LOCATIONS OF ALL EXISTING UTILITIES SHALL BE CHECKED BEFORE PROCEEDING WITH NEW WORK.
- NO CHANGES ARE TO BE MADE IN PLUMBING LAYOUT WITHOUT WRITTEN PERMISSION BY THE ARCHITECT OR ENGINEER.
- NO PIPING SHALL RUN EXPOSED IN FINISHED AREAS.
- ROUGH-IN DIMENSIONS OF TOILET FIXTURES MUST BE COORDINATED WITH THE GENERAL CONTRACTOR.
- PROVIDE SHUT-OFF VALVES FOR WATER HEATER BRANCH. PROVIDE DIELECTRIC FITTINGS OR COUPLINGS WHEREVER DISSIMILAR METALS ARE IN CONTACT.
- PROVIDE SHUT-OFF VALVES AT EACH FIXTURE AND AT EACH FLOOR (IF FIXTURES ARE STACKED) ON HOT AND COLD WATER SUPPLY PIPES.
- ALL ACCESS PANELS SHALL BE BY GENERAL CONTRACTOR. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR THEIR LOCATION.
- INSTALL ALL REQUIRED CLEANOUTS TO CLEAR EQUIPMENT AND FIXTURES.
- ALL WORK SHALL BE PROPERLY TESTED, BALANCED, CLEANED AND DISINFECTED. PROVIDE A ONE YEAR WARRANTY FROM DATE OF FINAL INSPECTION ON ALL PARTS AND LABOR.
- PITCH ALL WASTE AND SOIL PIPING AT MAXIMUM SLOPE POSSIBLE, BUT NOT LESS THAN 1/4" PER FOOT FOR PIPING UNDER 3" AND NO LESS THAN 1/8" PER FOOT FOR PIPING 3" AND GREATER. 6" AND LARGER PIPING CAN BE SLOPED AT 1/16" PER FOOT.
- PROVIDE ALL PIPE OPENINGS THROUGH PARTITIONS WITH PIPE SLEEVES WHERE PENETRATING FIRE RATED PARTITIONS. THE SPACE BETWEEN THE PIPE AND THE SLEEVE SHALL BE SEALED WITH FIRE STOPPING MATERIAL.
- PROVIDE CONDENSATE DRAIN FROM ROOF MOUNTED EQUIPMENT TO OPEN SITE DRAIN OR AS SHOWN ON DRAWINGS.
- ALL PIPING MATERIAL SHALL BE OF DOMESTIC MANUFACTURE AND SHALL COMPLY WITH THE BUY AMERICAN ACT.

PLUMBING TESTING NOTES

- ALL EQUIPMENT AND/OR SYSTEMS NOTED ON THE DRAWINGS TO REMAIN SHALL BE INSPECTED AND TESTED ON SITE TO CERTIFY WORKING CONDITION. A WRITTEN REPORT ON THE CONDITION OF ALL EQUIPMENT TO REMAIN, INCLUDING A COPY OF THE TEST RESULTS WITH RECOMMENDED REMEDIAL ACTIONS AND COSTS SHALL BE MADE BY THIS CONTRACTOR TO THE ARCHITECT/ENGINEER FOR REVIEW.
- PIPE COVER AND BACKFILLING:
 - AFTER HYDROSTATIC TEST, EVENLY BACKFILL ENTIRE TRENCH WIDTH BY HAND PLACING BACKFILL MATERIAL AND HAND TAMPING IN FOUR (4) INCHES COMPACTED LAYERS TO TWELVE (12) INCHES MINIMUM COVER OVER TOP OF JACKET. COMPACT TO 95 PERCENT MAXIMUM DENSITY.
 - EVENLY AND CONTINUOUSLY BACKFILL REMAINING TRENCH DEPTH IN UNIFORM LAYERS WITH BACKFILL MATERIAL.
 - DO NOT USE WHEELED OR TRACKED VEHICLES FOR TAMPING.
- PRESSURE TEST ALL DOMESTIC WATER PIPING AFTER INSTALLATION AND PRIOR TO BACKFILL OR COVER UP. RINSE PIPING SYSTEM OF PARTICULATE CONTAMINANTS, CAP AND SUBJECT TO STATIC WATER PRESSURE OF 125 PSIG FOR FOUR (4) HOURS. REPAIR LEAKS AND DEFECTS AND RE-TEST ANY PORTION OF PIPING SYSTEM THAT FAILS. PROVIDE WRITTEN TEST REPORT INCLUDING DATE AND TIME OF TEST, PASS OR FAIL INDICATION, SUMMARY OF REMEDIAL WORK REQUIRED AND DATE AND TIME OF EACH RE-TEST.
- PRIOR TO COVER UP, WATER PIPE, SANITARY PIPE, AND GAS PIPING SHALL BE PRESSURE TESTED. TESTS SHALL BE WITNESSED BY CONSULTANT AND OWNER. NOTIFY OWNER 48 HOURS PRIOR TO TEST. TEST SHALL BE WITNESSED BY CLIENT PLUMBING TECHNICIAN.
- UPON COMPLETION OF THE SANITARY PIPING SYSTEM, THE CONTRACTOR SHALL NOTIFY ENGINEER AND OWNER TO OBSERVE A SMOKE TEST OF THE SYSTEM. SMOKE TESTING SHALL BE PERFORMED ON SANITARY PIPING SYSTEM TWICE DURING CONSTRUCTION.
- ACID WASTE PIPING SYSTEMS:
 - WATER TEST SHALL BE APPLIED TO THESE DRAINAGE SYSTEMS EITHER IN THEIR ENTIRETY OR IN SECTIONS AS REQUIRED, AFTER ROUGH PIPING HAS BEEN INSTALLED. IF THE SYSTEM IS TESTED IN SECTIONS, EACH OPENING SHALL BE TIGHTLY CLOSED EXCEPT THE HIGHEST OPENING IN THE SECTION UNDER TEST. ALL SECTIONS SHALL BE TESTED WITH A MINIMUM OF 10 FEET HEAD OF WATER. IN TESTING SUCCESSIVE SECTIONS AT LEAST THE UPPER 10 FEET OF THE NEXT PRECEDING SECTION SHALL BE TESTED SO THAT NO JOINT OF PIPING IN THE BUILDING EXCEPT THE UPPERMOST 10 FEET OF THE SYSTEM SHALL BE SUBMITTED TO A TEST OF LESS THAN 10 FEET OF HEAD OF WATER. THE WATER SHALL BE KEPT IN THE SYSTEM FOR AT LEAST 30 MINUTES BEFORE INSPECTION STARTS. THE SYSTEM SHALL THEN BE MADE TIGHT AT ALL POINTS.
 - ANY POINTS OF THE DRAINAGE SYSTEMS TO BE TESTED WITH AIR INSTEAD OF WATER SHALL BE MADE BY ATTACHING AN AIR COMPRESSOR TESTING APPARATUS TO ANY SUITABLE OPENING AND AFTER CLOSING ALL OTHER INLETS OR OUTLETS, FORCING AIR INTO THE SYSTEM UNTIL THERE IS A MINIMUM GAUGE PRESSURE OF 5 PSI. THIS PRESSURE SHALL BE HELD WITHOUT THE INTRODUCTION OF ADDITIONAL AIR FOR A PERIOD OF AT LEAST 30 MINUTES.
 - EXTERIOR CONNECTIONS SHALL BE TESTED AS PART OF THE INTERIOR SYSTEMS.
 - ADDITIONAL TESTS:
 - PROVIDE ALL ADDITIONAL TESTS SUCH AS SMOKE OR PRESSURE TESTS AS REQUIRED BY THE REGULATIONS OR AS DIRECTED BY AUTHORITIES MAKING THE INSPECTION.
 - PROVIDE FOR ANY REPEATED TEST AS DIRECTED BY THE OWNER'S REPRESENTATIVE, TO MAKE ALL SYSTEMS TIGHT AS REQUIRED.
 - VISUAL INSPECTIONS OF JOINTS, VALVES, ETC. SHALL BE MADE AS DIRECTED BY THE ENGINEER.
 - PRESSURE TEST NATURAL GAS PIPING IN ACCORDANCE WITH NFPA 54. PRESSURE TEST PRIOR TO BACKFILL, MINIMUM 50 PSI FOR 24 HOURS.



ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608
ARCHITECT	BA & ARCHITECTS 1111 N. LOOP WEST SUITE 1000 SAN ANTONIO, TX 78205 210-462-0000
ARCHITECT	LEAF ENGINEERS 1801 Main St, Suite 100 San Antonio, TX 78203 210-491-8800





WFAC Black Box Addition PKG 1

1801 Main St, Suite 100
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



ALAMO COLLEGES
ST. PHILIP'S COLLEGE



CLIENT	Alamo Colleges	
DATE	06/14/2024	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	1	

KEYNOTES




- P3 4" WASTE PIPING DOWN FROM FLOOR ABOVE.
- P5 2" VENT UP AND 3" WASTE DOWN.
- P6 2" VENT UP AND 4" WASTE DOWN.
- P8 2" WASTE PIPING DOWN FROM SHOWER DRAIN ABOVE.
- P9 3" WASTE PIPING DOWN FROM FLOOR DRAIN ABOVE.
- P10 4" WASTE PIPING DOWN FROM FLOOR SINK ABOVE.
- P11 4" WASTE DOWN FROM WATER CLOSET ABOVE.
- P12 4" WASTE PIPING DOWN FROM FLOOR CLEAN OUT ABOVE.
- P13 2" WASTE DOWN FROM LAV/SINK ABOVE.
- P14 4" WASTE DOWN FROM WCO ABOVE.
- P17 3" WASTE DOWN FROM MOP SINK.
- P18 2" WASTE DOWN FROM URINAL.
- P20 2" WASTE DOWN FROM WASHING MACHINE BOX.
- P21 2" WASTE DOWN FROM DRINKING FOUNTAIN.
- P28 SANITARY SEWER PIPING STUB-OUT. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P29 STORM WATER PIPING STUB-OUT. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P34 REFER TO SPECIFICATIONS FOR ESP-1
- P109 FORCED MAIN FROM SUMP PUMP IN CRAWL SPACE.
- P110 SUMP PUMP DISCHARGE CONNECT TO GRATE INLET. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P111 PROVIDE DUPLEX SUMP PUMP MODEL EQUAL TO STANCOR SEW-150 200/3PH 100 GPM @ 20' OF HEAD.
- P112 ELEVATOR DISCHARGE PIPING UP TO OIL SEPARATOR.
- P113 2" FORCED MAIN TO OIL SEPARATOR.
- P115 ELEVATOR SUMP PUMP ESP-1. PUMP TO BE EQUAL TO LIBERTY PUMP 280 50 GPM, 14' HEAD, 1-1/2" DISCHARGE 1/2HP, 115V/1PH.



ARCHITECT PBK Architects, Inc.
 SAN ANTONIO
 601 N. W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-829-0123 P
 210-829-0578 F
 TX Firm BR 1650
 ASSOCIATE ARCHITECT
 DONALD C. RICHARDS
 6152
 07/08/2024
 LEAF ENGINEERS
 F-18672



WFAC Black Box Addition PKG 1
 1801 Main, Luther King Dr.,
 San Antonio, TX 78203
 90%CD - IFR



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
07/08/2024	230462	
DRAWING HISTORY		
No.	Description	Date
1	CITY COMMENTS	06/05/2024
2	CITY COMMENTS	06/12/2024
3	CITY COMMENTS	06/24/2024
4	CITY COMMENTS	07/08/2024

90%CD - IFR
 BUILDING NUMBER 1


CRAWLSPACE PLUMBING PLAN

PU-101-A


File Path: Autocad Docs://Name CS_230462_Al Philip College WBB AddP23 WFAC - Blackbox Addition - A03.rvt

CHECKED BY:
 Checker
 DRAWN BY:
 Author
 Plot Stamp:
 7/8/2024 7:29:33 AM

5
1



1 1ST LEVEL ENLARGED PLUMBING PLAN - AREA C
SCALE: 1/4" = 1'-0"



2 1ST LEVEL ENLARGED PLUMBING PLAN - AREA D
SCALE: 1/4" = 1'-0"

KEYNOTES

- P3 4" WASTE PIPING DOWN FROM FLOOR ABOVE.
- P6 2" VENT UP AND 4" WASTE DOWN.
- P10 4" WASTE PIPING DOWN FROM FLOOR ABOVE.
- P39 ROOF DRAIN PIPING DOWN TO BELOW FLOOR. SIZE AS NOTED.
- P45 3/4" COLD WATER, 3/4" HOT WATER DOWN AND 2" VENT UP.
- P46 3/4" COLD WATER DOWN AND 2" VENT UP.
- P48 3/4" COLD WATER AND 3/4" HOT WATER DOWN TO SHOWER VALVE.
- P49 1 1/4" COLD WATER DOWN AND 2" VENT UP.
- P71 HOT WATER DOWN IN CHASE / WALL SIZE AS NOTED.
- P73 PROVIDE BALANCING VALVE.
- P114 PROVIDE ELEVATOR SLUMP SYSTEM EQUAL TO PARK ELYC-100 SEPARATOR MODEL ESC-100 50 GPM FLOW RATE 100 GALLON CAPACITY.






ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N. W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P TX Firm SR 1659
ASSOCIATE ARCHITECT	W.A. ARCHITECTS 1710 S. W. 18th St. MIAMI, FL 33135
DESIGNER	LEAF ENGINEERS 1801 Main, Luber King Dr. San Antonio, TX 78203
MECHANICAL ENGINEER	LEAF ENGINEERS 1801 Main, Luber King Dr. San Antonio, TX 78203
ELECTRICAL ENGINEER	LEAF ENGINEERS 1801 Main, Luber King Dr. San Antonio, TX 78203
PLUMBING ENGINEER	LEAF ENGINEERS 1801 Main, Luber King Dr. San Antonio, TX 78203
MECHANICAL PROFESSIONALS	LEAF ENGINEERS 1801 Main, Luber King Dr. San Antonio, TX 78203
ELECTRICAL PROFESSIONALS	LEAF ENGINEERS 1801 Main, Luber King Dr. San Antonio, TX 78203
PLUMBING PROFESSIONALS	LEAF ENGINEERS 1801 Main, Luber King Dr. San Antonio, TX 78203



WFAC Black Box Addition PKG 1


1801 Main, Luber King Dr.,
San Antonio, TX 78203
90%CD - IFR




CLIENT		Alamo Colleges
DATE	07/08/2024	PROJECT NUMBER
DRAWING HISTORY		230462
No.	Description	Date
4	CITY COMMENTS	07/08/2024
90%CD - IFR		
BUILDING NUMBER	1	

PLUMBING ENLARGED PLAN


P-401




1 DOMESTIC COLD WATER ENTRY
 SCALE: N.T.S.



2 FIRE PUMP
 SCALE: N.T.S.



3 DUPLEX PACKAGE PUMPING SYSTEM
 SCALE: N.T.S.



- KEYED NOTES:**
- STANCOR MODEL SE50A SUBMERSIBLE EFFLUENT PUMP, 50 GPM @20TDH, 1/2" HP, 115 VOLT, 2" DISCHARGE CONNECTION.
 - MOLDED FRP GRATING 1 1/2" SQUARE PATTERN, 1 1/2" THICK (RYAN-HERCO 1962-330) SUPPORTED BY FIBERGLASS ANGLES (1 1/2" X 1 1/2" RYAN-HERCO 1912-010). CUT AROUND PRESERVING TO ALLOW REMOVAL OF GRATE.
 - ELEVATOR SUMP PUMP CONTROL ALARM PANEL (EQUAL TO SJE-RHOMBUS-MODEL 115 CONTROL PANEL WITH HIGH WATER SENSOR/ALARM (LIGHT, AUDIBLE HORN), HOA PUMP SWITCHING, SILENCE SWITCHES, AUXILIARY ALARM CONTACTS, POWER-ON (ALARM FOR HIGH-WATER SENSOR LIGHT).
 - PROVIDE WATERPROOF SEAL EQUAL TO LINK-SEAL.
 - POWER, HIGH WATER ALARM, AND PUMP ON CABLES.
 - HIGH LIQUID ALARM FLOAT WITH CLAMP DEVICE TO MOUNT TO PUMP DISCHARGE PIPING.
 - DISCHARGE TO NEAREST FLOOR DRAIN OR MOP SINK WHERE AVAILABLE.
 - ROUTE 4" VENT RISER FULL SIZE TO ROOF. PROVIDE GOOSENECK WITH INSECT SCREEN.
 - OIL SEPARATOR SHALL BE PARK ENVIRONMENTAL EQUIPMENT ES-100.
 - CONCRETE HOUSEKEEPING PAD. EXTEND PAD 6" ON ALL SIDES.
 - SEPARATOR BASIN.
 - REMOVABLE STEEL COVER WITH RECESSED HANDLES, NEOPRENE GASKET, & SECURED W/ SS BOLTS.
 - 2", 3" OR 4" NPT STEEL FULL CPLG.
 - TYPICAL BAFFLE.
 - OLEOPHILIC COALESCING PLATE PACK TO SEPARATE OIL & SOLIDS.
 - 1" ADJUSTABLE SKIMMER.
 - 2" OIL DRAIN - NPT FULL CPLG W/ PLUG.
 - 2" VENT - NPT HALF CPLG.
 - 2" DRAIN - NPT HALF CPLG W/ PLUG.

- GENERAL NOTES:**
- LOCAL CODES TYPICALLY USE THE ASME A17.1/CSA B 44-07 - "SAFETY CODE FOR ELEVATORS AND ESCALATORS" FOR ELEVATOR DESIGNS. THE ASME STANDARD REQUIRES THAT EACH ELEVATOR SHAFT HAVE A PUMP/DRAIN CAPABLE OF REMOVING A MINIMUM OF 3000 GALLONS (50 GALLONS) OF WATER PER SHAFT. THIS WASTEWATER SHOULD BE TREATED PRIOR TO DISCHARGING INTO THE LOCAL SEWER. THE PARK ELEVATOR SEPARATOR IS DESIGNED FOR THIS PURPOSE. SERIES ES COALESCING PLATE SEPARATORS ARE DESIGNED TO RECEIVE OILY WASTEWATER BY GRAVITY OR PUMP FLOW AND PROCESS IT ON A ONCE-THRU OR CIRCULATING BASIS. THERE ARE NO MOVING PARTS TO FAIL OR THAT REQUIRE EXPENSIVE MAINTENANCE.
 - PRE-ENGINEERED COALESCING MEDIA PACKS ARE UTILIZED FOR ENHANCED SEPARATION WHICH PROVIDE SUPERIOR PERFORMANCE COMPARED TO OTHER SEPARATORS WHICH DEPEND ON BAFFLES ONLY.
 - THE PARK ES SEPARATOR IS SPECIFICALLY DESIGNED FOR ELEVATOR SUMPS WHICH ARE SUBJECT TO CONTAMINATION FROM THE ELEVATOR EQUIPMENT. THE SEPARATOR WILL REMOVE HYDRAULIC AND LUBRICATION OILS WHICH COULD BE HARMFUL TO THE CITY SEWER.
 - THE PARK ES SEPARATOR ONLY REQUIRES MINIMAL MAINTENANCE. OILS ARE REMOVED FROM THE SEPARATOR BY A LICENSED WASTE DISPOSAL COMPANY.
 - DESIGN AND ROUTE ALL ELEVATOR RELATED WORK PER ASME 17.1, (ELEVATOR CODE) LATEST VERSION.
 - GUARANTEED PERFORMANCE FOR CODE MAXIMUM OIL CONCENTRATION (SANITARY SEWER 200 PPM).
 - ALL CONTROL CABLING TO BE ROUTED IN CONDUIT.
- SEQUENCE OF OPERATION:**
- WATER ENTERS SUMP.
 - FLOAT SWITCH #1 INITIATES SUMP PUMP AND ALARM AT JANITOR'S OFFICE.
 - WATER DISCHARGES TO OIL SEPARATOR AT LOCATION INDICATED ON DWGS.
 - WHEN WATER CONTINUES TO RISE, HIGH WATER ALARM FLOAT SWITCH #2 SOUNDS ALARM AT JANITOR'S OFFICE.
 - PUMP EMPTIES PIT AND FLOAT SWITCH #1 DEACTIVATES PUMP AND ALARM.

PLUMBING DETAILS
 P-602
 FOR BLUEBEAM LABELING OCR:
 File Path: Autodeskt Dcs://Name CS_230462_A1 Philip College WBB AddP23 WFAC - Blackbox Addition - A03.rvt
 CHECKED BY: [Blank]
 CHECKER: [Blank]
 DRAWN BY: [Blank]
 AUTHOR: [Blank]
 Plot Stamp:
 7/8/2024 7:29:34 AM

GROUP SYMBOL DESCRIPTION

DEVICES

NOTE: 1. EVERY SYMBOL SHOWN ON LEGEND MAY NOT APPEAR ON DRAWINGS. REFER TO GENERAL ELECTRICAL NOTES FOR WALL-MOUNTED DEVICE MOUNTING HEIGHTS AND BACK BOX REQUIREMENTS.

FIRE ALARM LEGEND

Table with 3 columns: SYMBOL, DESCRIPTION. Includes items like FOOT ADDED TO ANY SYMBOL, MANUAL FIRE ALARM PULL STATION, FIRE ALARM SPEAKER OR HORN, VISUAL ALARM STROBE, SMOKE DETECTOR, BEAM SMOKE DETECTOR, FIRE FIGHTER'S TELEPHONE JACK, etc.

GENERAL FIRE ALARM NOTES

- 1. ALL 120V POWER REQUIRED FOR THE FUNCTIONALITY OF THE FIRE ALARM SYSTEMS SHALL BE A DEDICATED CIRCUIT AND ON EMERGENCY POWER WHEN AVAILABLE. THE INSTALLING CONTRACTOR OF EACH SYSTEM SHALL BE RESPONSIBLE FOR PROVIDING THEIR OWN 120V POWER REQUIREMENTS FOR ALL REMOTE POWER SUPPLIES. THE GENERAL CONTRACTOR'S LICENSED ELECTRICAL SUBCONTRACTOR SHALL COORDINATE THE ELECTRICAL PANEL LOCATIONS AND AVAILABLE SPACE DEDICATED FOR THE CONTRACTOR'S SYSTEM REQUIREMENTS. (TYPICAL) ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ALL POWER TOMAIN CONTROL PANELS AND ALL HEAD END EQUIPMENT. SYSTEM INSTALLERS SHALL COORDINATE LOCATION AND CONNECTION OF CONTROL PANEL AND HEAD END POWER WITH THE PROJECT'S ELECTRICAL CONTRACTOR.

AUDIO & VIDEO GENERAL NOTES

- 1. ALL 120V POWER REQUIRED FOR THE FUNCTIONALITY OF EACH SYSTEM SHALL BE A DEDICATED CIRCUIT. THE INSTALLING CONTRACTOR'S LICENSED ELECTRICAL SUBCONTRACTOR SHALL COORDINATE ELECTRICAL PANEL LOCATIONS AND AVAILABLE SPACE DEDICATED FOR THE CONTRACTOR'S SYSTEM REQUIREMENTS (TYPICAL). ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ALL POWER TO MAIN CONTROL PANELS AND ALL HEAD END EQUIPMENT.

TECHNOLOGY PLAN GENERAL NOTES

- 1. ALL 120V POWER REQUIRED FOR THE FUNCTIONALITY OF THE TELECOMMUNICATION NETWORK, AUDIO/VIDEO, SECURITY AND FIRE ALARM EQUIPMENT SHALL BE A DEDICATED CIRCUIT AND ON EMERGENCY POWER WHERE POSSIBLE. CONTRACTOR SHALL COORDINATE AND INSTALL ALL 120V POWER REQUIREMENTS AND LOCATIONS AS REQUIRED FOR ALL EQUIPMENT (TYPICAL).

SECURITY SYSTEMS LEGEND

Table with 3 columns: SYMBOL, DESCRIPTION. Includes items like INTERIOR VIDEO SURVEILLANCE CAMERA, EXTERIOR WALL MOUNTED CAMERA VIDEO SURVEILLANCE CAMERA, 360 DEGREE CEILING MOUNTED MOTION DETECTOR, INTRUSION DETECTION SYSTEM ARMI/DSARM KEYPAD, PANIC BUTTON, etc.

- NOTE: 1. EVERY SYMBOL SHOWN ON LEGEND MAY NOT APPEAR ON DRAWINGS. REFER TO GENERAL ELECTRICAL NOTES FOR WALL-MOUNTED DEVICE MOUNTING HEIGHTS.

BDA/DAS SYSTEMS LEGEND

Table with 3 columns: SYMBOL, DESCRIPTION. Includes items like BI-DIRECTIONAL AMPLIFIER (BDA) SIGNAL BOOSTER, BDA ANNUNCIATOR PANEL.

- NOTE: 1. EVERY SYMBOL SHOWN ON LEGEND MAY NOT APPEAR ON THE DRAWINGS. REFER TO THE SPECIFICATIONS AND THE TECHNOLOGY SYSTEMS GENERAL NOTES FOR INSTALLATION REQUIREMENTS.

TECHNOLOGY LEGEND

Table with 3 columns: SYMBOL, DESCRIPTION. Includes items like INDICATES THE LOCATION OF A NEW TECHNOLOGY OUTLET, INDICATES THE LOCATION OF A CEILING MOUNTED OUTLET, INDICATES THE LOCATION OF A FLOOR MOUNTED OUTLET, etc.

- NOTE: 1. EVERY SYMBOL SHOWN ON LEGEND MAY NOT APPEAR ON DRAWINGS. REFER TO GENERAL ELECTRICAL NOTES FOR WALL-MOUNTED DEVICE MOUNTING HEIGHTS.





ARCHITECT PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216



INDICATES THE LOCATION OF ASSISTED LISTENING ANTENNA. PROVIDE WIREGUARD ON ALL DEVICES INSTALLED IN GYMNASIUMS. ELECTRICAL CONTRACTOR SHALL PROVIDE 2 GANG EXTRA DEEP BOX, FLUSH MOUNT @ 12" A.F.F. UNLESS OTHERWISE NOTED.

WFAC Black Box Addition PKG 1 1801 Marlin Luther King Dr., San Antonio, TX, 78203. ISSUE FOR CONSTRUCTION




CLIENT Alamo Colleges DATE 2024/06/14 PROJECT NUMBER 230462

Table with 3 columns: No., Description, Date. Includes drawing history entries.

ISSUE FOR CONSTRUCTION BUILDING NUMBER 1 TECHNOLOGY SYSTEM NOTES AND LEGENDS

ISSUE FOR CONSTRUCTION



1 SITE TECHNOLOGY PLAN
 SCALE: 1" = 30'-0"

TECHNOLOGY KEYNOTES



- TS1 INDICATES THE APPROXIMATE LOCATION OF THE NEW BUILDING IDF. CONDUITS SHALL BE STUB EVENTLY AT +8 A.F.F TO ENTER THE NEW MDF/IDF
- TS3 CONTRACTOR TO INSTALL TWO (2) FOUR INCH (4") CONDUIT WITH A PULLING LINE FROM THIS MANHOLE ALL THE WAY TO THE NEW IDF ROUTED AT 4 B.F.G. PROVIDE TWO (2) 3-CELL MAXCELL INNERDUCT IN EACH CONDUIT. THE UNDERGROUND CONDUIT PATHWAY WILL BE INSTALLED BY THE DIV 26 CONTRACTOR.
- TS4 INDICATES THE APPROXIMATE LOCATION OF AN EXISTING MANHOLE
- TS5 INDICATES THE APPROXIMATE LOCATION OF AN EXISTING CONDUIT PATHWAY TO BE REMOVED CONTRACTOR SHALL PULL BACK EXISTING FIBER FROM THE EXISTING MANHOLE ALL THE WAY BACK TO THE PREVIOUS BOX. FIBER TO BE RE-USED IF POSSIBLE. CONTRACTOR WILL RE-ROUTE THE EXISTING FIBER AND FUSE SPLICE AT THE SAME BOX IT WAS PULLED FROM THE BEGINNING JUST FROM A DIFFERENT PATHWAY. CONTRACTOR SHALL PAY FOR ANY DAMAGE TO EXISTING FIBER.
- TS6 INDICATES THE APPROXIMATE LOCATION FOR THE NEW PATHWAY FOR THE EXISTING FIBER TO BE RE-ROUTED TO MAINTAIN THE SERVICE UP AND RUNNING. CONTRACTOR TO FIELD VERIFY THE AMOUNT OF CONDUIT NEEDED FOR THIS NEW ROUTE TO WORK AS THE PREVIOUS.
- TS8 INDICATES THE APPROXIMATE LOCATION OF THE EXISTING CAMPUS MDF. CONDUITS SHALL BE STUBBED EVENTLY AT +8 A.F.F TO ENTER THE MDF/IDF.
- TS9 CONTRACTOR TO PULL A NEW ONE (1) 24-STRAND SINGLE MODE FIBER OUTDOOR/ARMORED-RATED FROM THE EXISTING CAMPUS MDF INTO THE NEW BLACK BOX BUILDING IDF. PROVIDE TWO (2) 3-CELL MAXCELL INNERDUCT IN EACH CONDUIT.
- TS10 CONTRACTOR TO FIELD VERIFY THE EXISTING PATHWAY AND REROUTE THE EXISTING FIBER INTO THE NEW PATHWAY PRIOR TO ANY CONSTRUCTION TO MAINTAIN THE NETWORK ALIVE. CONTRACTOR TO LABEL ALL SPOOLS IN THE MANHOLE ACCORDING TO ACC STANDARDS AND REMOVED ANY NON-WORKING CABLING ALL THE WAY TO THE CAMPUS MDF PATHWAY.
- TS11 CONTRACTOR TO REMOVE ALL NON-WORKING LOW VOLTAGE CABLE ALL THE WAY TO THE CAMPUS MDF DURING THE NEW FIBER PULLING FOR THIS PROJECT.



ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-5578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	B&A ARCHITECTS 2025 210-829-0123 P 210-829-5578 F TX Firm BR 1608
CONSULTANT	LANDSCAPE 2025 210-829-0123 P 210-829-5578 F TX Firm BR 1608
CONSULTANT	LANDSCAPE GROUP 2025 210-829-0123 P 210-829-5578 F TX Firm BR 1608
CONSULTANT	LUNY & FRANK ENGINEERING 2025 210-829-0123 P 210-829-5578 F TX Firm BR 1608
CONSULTANT	MECHANICAL 2025 210-829-0123 P 210-829-5578 F TX Firm BR 1608
CONSULTANT	ELECTRICAL 2025 210-829-0123 P 210-829-5578 F TX Firm BR 1608
CONSULTANT	MECHANICAL 2025 210-829-0123 P 210-829-5578 F TX Firm BR 1608
CONSULTANT	MECHANICAL 2025 210-829-0123 P 210-829-5578 F TX Firm BR 1608



WFAC Black Box Addition PKG 1



CLIENT	Alamo Colleges	
DATE	2024/06/14	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
 BUILDING NUMBER 1
SITE TECHNOLOGY PLAN

TS-101